

**Illinois State Water Survey**  
**COOPERATING TECHNICAL PARTNERS (CTP)**  
**FLOOD RISK PROJECT**  
**MAPPING ACTIVITY STATEMENT (MAS)**

**MAS No. ISWS20-13 Peoria Data Development Additional Tasks**

The Flood Risk Project described in this MAS dated June 2020 shall be completed in accordance with the CTP Partnership Agreement dated September 9, 2013 between Illinois State Water Survey (herein referred to as “CTP”) and the Federal Emergency Management Agency (FEMA).

**DISCLAIMER (do not delete): In recognition of the MIP Studies Redesign which was deployed in June 2017, FEMA Region V has made an effort to update the accompanying “R5\_MAS\_SOW\_Workbook” to align with terminology, projects, purchases and tasks in the redesigned MIP. The Region acknowledges that the signed SOW may or may not contain the required sections, tables, scope or terminology that is fully aligned with the FEMA Region V Workbook. Due to the reasons, the “R5\_MAS\_SOW\_Workbook” will be treated as the sole source for creating and obligating projects, purchases and tasks in the redesigned MIP.**

## ***CONTENTS***

|                                                                    |           |
|--------------------------------------------------------------------|-----------|
| SECTION 1—OBJECTIVE AND SCOPE .....                                | 4         |
| SECTION 3 – PERIOD OF PERFORMANCE.....                             | 17        |
| SECTION 4 – FUNDING/LEVERAGE (For CTP, OFA, and/or Community)..... | 17        |
| SECTION 5 – STANDARDS.....                                         | 18        |
| SECTION 6 – SCHEDULE.....                                          | 19        |
| SECTION 7 – CERTIFICATIONS .....                                   | 21        |
| SECTION 8 – TECHNICAL ASSISTANCE AND RESOURCES .....               | 21        |
| SECTION 9 – CONTRACTORS .....                                      | 21        |
| SECTION 10 – REPORTING .....                                       | 22        |
| SECTION 11 – PROJECT COORDINATION .....                            | 23        |
| <b>SECTION 12 – PROTECTION OF PRIVACY INFORMATION.....</b>         | <b>23</b> |
| SECTION 13 – POINTS OF CONTACT .....                               | 25        |

## **SECTION 1—OBJECTIVE AND SCOPE**

The objective of the Flood Risk Project documented in this Mapping Activity Statement is to develop and/or support flood hazard data and program-related tasks through completing technical risk analysis and mapping activities. These activities may or may not result in a new or updated Flood Insurance Rate Map (FIRM) and Flood Insurance Study (FIS) report for one or more communities within the project area.

### *Introduction*

The objective of this project is to advance the development of a countywide Digital Flood Insurance Rate Maps (FIRMs) for Peoria County. Effective FIRMs for Peoria County, Illinois, are still in paper format. A series of projects have been funded advancing data development to meet FEMA standards for digital FIRM production: ISWS11-16 Zone A H&H; DFIRM database, ISWS12-05 Outreach, and ISWS13-05 Preliminary Maps and Post Processing. The project did not advance to Preliminary as standards had changed and unverified Zone AE streams required restudy and issues related to one levee were unresolved. A number of levees had been identified over the course of the project, only the Lonza and Evonik remained an outstanding issue to be resolved by FEMA Region 5 at the end of project work under ISWS13-05.

The latest project activity was funded in FFY2018 under MAS ISWS18-04 data development to QR3. MAS ISWS18-04 includes restudy of unverified Zone AE streams in Peoria County developing new hydrologic and hydraulic models. Also, a hydrologic & hydraulic model for Fargo Run and its tributaries, prepared by others, will be updated with newer topographic data, structures, and a floodway computed and mapped as a Zone AE. MAS ISWS18-04 includes a total of 70 miles of Zone AE with floodway and 1 mile of Zone A using 2012 LiDAR topographic data. During the course of the data development and preparation of work maps, issues were uncovered that had not been identified or funded. This MAS covers those tasks needed to advance the project to QR3 that are not yet funded.

There are three tasks that must be performed to allow for advancement to QR3.

#### **1. Kickapoo Creek Embankments Modeling (Data Development Task):**

Under MAS ISWS 18-04, the ISWS was contracted to restudy Kickapoo Creek. New hydrology was performed, resulting in flows doubling in the downstream area. As flows from Kickapoo Creek enter the vast Illinois River floodplain, they encounter numerous embankments (e.g., I-74 Interstate and the embankments at the Keystone Steel manufacturing facility). Traditional 1-D modeling funded under MAS ISWS18-04 is not capable of accurately determining the complex flow paths and hydraulic impacts resulting from these embankments. A 2-D model is needed to reveal the effects of the embankments on the Kickapoo flow. Preliminary results indicate the embankments restrict, re-direct and split the flow as it makes its way to the Illinois River. With a better understanding of how the flow moves in this area due to the 2-D model results, 1-D models will be constructed to model the split flows in this area and used to present the modeling results on the workmaps for a Flood Risk Review Meeting. It is expected that 1 to 2 additional miles of Base level (B) Zone A models will need to be prepared. The preliminary 2-D modeling results were shared by the ISWS on a webinar call, on January 30, 2020, with FEMA/IDNR-OWR and the RSC (STARR II).

Additional funds are needed under Hydraulic Data Development Task for the advanced 2-D modeling and revision of 1-D hydraulic models and additional miles of study. Embankments known as Keystone levee are privately owned and lie primarily within the Village of Bartonville. The owners did NOT pursue levee accreditation or a LAMP investigation when contacted in

2015. The Village of Bartonville was informed but declined to take any action at the time. Alteration of the flood hazard mapping due to the updated modeling of Kickapoo Creek increases the risk of a challenge to the updated mapping and potential interest in options for treatment of the embankments.

2. Levees in Peoria County (Project Risk Identification and Mitigation Task):

ISWS has proactively tracked the status of levee accreditation/non-accreditation, mapping impacts, and documentation requirements for the DFIRM database. During the course of preparing hydraulic models, two levees were newly identified, Defenbaugh and Taylor-Chapman Levees. A levee tracking sheet and associated map exhibit were updated by ISWS and provided to FEMA R5 and the RSC (STARR II) for review on October 17, 2019, and discussed in the October 24, 2019 call with FEMA and the RSC. A revised exhibit was prepared by ISWS and provided on October 28, 2019 based on the call discussion.

Resolution of modeling and mapping issues related to newly identified levees as well as confirmation that other levees already identified (levee tracking sheet) have had investigations meeting current FEMA protocols is necessary to proceed to workmaps. Additional funds for Project Risk Identification and Mitigation are requested.

3. Illinois River Floodplain Redelineation (Floodplain Mapping: Redelineation Data Capture Task):

The Illinois River study from the USACE Upper Mississippi River Flow Frequency Study (UMRFFS) circa 2004 has been used for all DFIRM updates to counties bordering the Illinois River. Although this study would no longer score as valid, no other alternative is available and incorporation into the Peoria DFIRM would provide continuity until a full update of the Illinois River is performed. The floodplain delineation and incorporation into the DFIRM database of the 2004 USACE UMRFFS was performed under ISWS13-05 work. The Illinois River study from 2004 was delineated using a DTM developed by EarthData International of Maryland, LLC from aerial photography and photogrammetry (DEM/DTM Project 1998-2001). Several streams (tributary to the Illinois River) are being studied as revised Zone AE's with floodway and are using the newer 2012 Countywide LiDAR topographic data for cross section overbank geometry and floodplain delineation. The floodplains of these streams must tie into the floodplain of the Illinois River; however, inconsistencies between the older lower resolution topography and the 2012 LiDAR cannot be resolved. A redelineation of 46 miles of the Illinois River floodplain using the 2012 LiDAR topographic data is necessary to meet FEMA standards.

Funding for the Floodplain Mapping: Redelineation Data Capture Task is requested.

The watersheds and jurisdictions in which Flood Risk Projects will be performed, as well as their applicable project type/activities, are summarized in Table 1.1: Flood Risk Project Watersheds and Jurisdictions. All applicable project activities should be identified in the last column of the table for each watershed, county/parish or community listed in Table 1.1 (e.g., Discovery only, Discovery and Flood Risk Products, FIRM/FIS updates, Prelim Distribution, Post-Preliminary Processing). Watershed Reports will be created and distributed to counties/parishes and communities identified as including Discovery in the Project Type.

**Table 1.1: Flood Risk Project Watersheds and Jurisdictions**

| <b>Watershed</b>                         | <b>Geographic Footprint</b> | <b>Counties/Parishes and Communities Included in Project</b> | <b>Project Type</b>    |
|------------------------------------------|-----------------------------|--------------------------------------------------------------|------------------------|
| Lower Illinois-Lake Chautauqua Watershed | 07130003                    | Peoria County                                                | Hydrology & Hydraulics |
| Lower Illinois-Senachwine Lake Watershed | 07130001                    | Peoria County                                                | Hydrology & Hydraulics |

This Flood Risk Project will be completed by the following entities:

- **Illinois State Water Survey.**

The CTP shall notify FEMA and all applicable parties of all meetings with community officials, and other relevant meetings, between three and six weeks prior to the meeting (with as much notice as possible). FEMA and/or its contractor may or may not attend the community meetings.

The CTP shall maintain an archive of all data submitted. All supporting data must be retained for three years from the date a funding recipient submits its final expenditure report to FEMA. The CTP must demonstrate to FEMA compliance with Subpart 24.1 of the Federal Acquisition Regulation (FAR) related to the handling of Personally Identifiable Information (PII) associated with the Activities listed in this MAS.

The CTP is responsible for providing a Quality Management Plan (QMP) to include an independent Quality Assurance/Quality Control (QA/QC) plan for all assigned activities. The CTP will submit a Summary Report that describes and provides the results of all automated or manual QA/QC review steps. The report should include the process for all assigned activities. The QMP is delivered directly to the FEMA Regions.

Independent QC review activities may be performed by the CTP or FEMA's contractor at the discretion of FEMA. If the CTP will be responsible for the QC review, the entity that will perform QC should be identified in this MAS. The CTP will need to submit its QC plan to the Regional Project Officer for approval.

Please note FEMA will also be performing periodic audits and overall study/project management to promote quality, including National Quality Reviews (QR) required per FEMA standards for all Flood Risk Projects. Whether or not the CTP performs the Independent QC review mentioned in the preceding paragraph, the CTP will be responsible for addressing any and all comments resulting from National QRs and any additional independent QA reviews required by the FEMA Regional Office, including re-submittal of deliverables as needed to pass technical or quality review. The CTP will submit regulatory products to FEMA's designated National QR reviewer (for QR 1-8 reviews) for review and approval prior to public issuance.

Metadata is required for certain activities. The FEMA current, applicable metadata guidelines will be followed.

FIRM-related tasks require a passing QC Report from FEMA's National FIRM database auto-validation tool, the Database Validation Tool (DVT) for QRs #1, #2, and #5 as required in FEMA standards. DVT can be found in the Mapping Information Platform tasks that correspond to the QRs: Draft FIRM Database Capture, Produce Preliminary Products Data Capture, and Final Mapping Products Data Capture. Training materials for this step are available on the Mapping Information Platform (MIP) at MIP User Care Training Materials.

FEMA will provide download/upload capability for data submittals through the MIP located at <https://hazards.fema.gov>. As each activity is completed, the data must be submitted to the MIP by the CTP or other designee. After data is submitted, a Validation task must be completed. Note that FEMA's designee will be assigned this task, not the CTP

The CTP assigned to the activity will respond to any comments generated as a result of the mandatory quality control checks by the Production and Technical Services (PTS) contractor. The PTS QC process is nationally funded and required on each non-PTS study.

In cooperation with the FEMA Project Officer, a Project Management Team (PMT) will be established by the CTP consisting of representatives from the CTP, FEMA's Regional Engineer, and other appropriate parties (e.g., FEMA contractors) at the discretion of FEMA. The PMT will be responsible for coordinating the activities identified in this MAS. The FEMA Region will be provided with documentation identifying the established PMT. The PMT will include representatives from the Illinois Department of Natural Resources/ Office of Water Resources, the FEMA Region 5 Engineer assigned to Illinois, and the Illinois State Water Survey (ISWS), Coordinated Hazard Assessment Mapping Program Section Head or their designee.

Responsible Mapping Partner: ISWS

Scope: Project Management is the active process of planning, organizing, and managing resources toward the successful accomplishment of predefined project goals and objectives. The CTP will coordinate with the FEMA Regional Office with respect to Project Management activities and technical mapping activities.

### **Earned Value Data Entry**

**The FEMA Mapping Information Platform (MIP) is designed to track the earned value of Flood Risk Projects. This information is automatically calculated by the MIP, using the actual cost and schedule of work performed, or "actuals," and comparing them to the expected cost and schedule of work performed, or "baseline."**

Once the FEMA Regional Office has funded a project, FEMA or its contractor will create the tasks in the MIP. This step establishes the baseline for the project in the MIP, using the cost and schedule information for each task as outlined in this document.

The MIP study application allows FEMA and the CTP to manage the status of these projects at a task level. The cost and schedule information, updated monthly by the CTP for each contracted task, is

compared to the baseline established for those tasks. This information is rolled up to a project level and monitored by the FEMA Region to assess progress and earned value.

Earned Value data entry involves updating cost, schedule, and performance (physical percent complete), and as of date in the MIP by the CTP each month for each assigned task.

Once the baseline has been established in the MIP, the CTP shall input the performance and actual cost to date for all tasks within each project for which the CTP is responsible. This must be completed at a minimum once every 30 days and at the completion of the task. When a task is completed and has been validated (if applicable), the CTP shall enter 100 percent complete, enter the actual completion cost, and the actual completion date within the Track Task Progress Workbench as applicable. The tasks will be available on the Track Progress workbench up to 90 days after the completion of the producer task in each purchase.

The MIP shall also be populated with appropriate leverage information regarding who (CTP or community) paid for the data provided and the amount of data used by the Flood Risk Project. The CTP will maintain a Schedule Performance Index (SPI) and Cost Performance Index (CPI) between 0.92 and 1.08. Special Problem Reports (SPR) explaining any variance must be submitted in a timely manner as required.

The CTP is required to report on the earned value of projects that are in the MIP monthly and must give explanations for variances outside of the tolerance defined above. FEMA Regional Offices must implement a Corrective Action Plan (CAP) when a CTP partner is outside of the tolerance. A CAP must define the reason for the variance and the intended resolution. FEMA Regional Offices must coordinate with FEMA Headquarters when CAPs are developed.

Program Management and overarching Community Outreach and Mitigation Strategies (COMS) SOW tasks are now tracked in the MIP. Cost and schedule performance measures must be defined and documented in those separate MAS or SOW. These measures must be used to monitor partner performance and to determine future funding eligibility. This exception only applies to tasks not able to be conducted or tracked in the MIP.

The Project Officer, as needed, may request additional information on status of the project on an ad hoc basis.

Standards: All PM work shall be performed in accordance with the standards specified in Section 5 – Standards.

Deliverables: The CTP shall deliver the following checked item(s) to the FEMA Regional Project Officer (please click/check the box of the deliverables included in this MAS):

|                                     |                                                                                                                                                                                                               |
|-------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <input checked="" type="checkbox"/> | Monthly earned value data reporting through the MIP with variance explanations to support management of technical mapping activities within specified time frame, for both Regulatory and Flood Risk Products |
| <input type="checkbox"/>            | Management of SPI/CPI performance for an organization                                                                                                                                                         |
| <input type="checkbox"/>            | Overall project Quality Management Plan including QA/QC maintenance information, such as maintaining a QA/QC log and providing a QA/QC approach to FEMA for review and approval                               |
| <input type="checkbox"/>            | Management of adherence to scope of work and quality of work for an organization                                                                                                                              |
| <input type="checkbox"/>            | Other: <b>{Insert additional details}.</b>                                                                                                                                                                    |

## Project Risk Identification and Mitigation

Responsible Mapping Partner: ISWS.

Risks to the planned completion of a project may come from various sources. Risks should be identified during the planning phase and monitored throughout the project, so that potential impact can be assessed, and solution strategies developed and implemented as needed.

**Table 1.3: Project Risk Identification**

| Project Risk                                                                                                                                                                                     | Potential Impact                                                   | Solution Strategy                                                                                                                                                                                                                                                                                   |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Community and Keystone Steel resistance to new delineation of Kickapoo Creek floodplain extent.                                                                                                  | Technical appeal and project delay.                                | Engage the community and embankment owner(s) in advance of the Flood Risk Review meeting to inform them of the proposed new studies and mapping. Incorporate technical comments from Flood Risk Review Meeting into the hydrologic and hydraulic models and continue coordination with communities. |
| Engagement with levee/ embankment owners (with the exception of Evonik / Lonza Levees) was completed 5 years ago. Resolution of levee status may be challenged under LAMP guidance issued later. | Technical appeal and project delay. Request for full LAMP process. | Re-engage the community and levee owners in advance of the Flood Risk Review meeting to review levee status findings and proposed floodplain mapping. FEMA R5 engage RSC to resolve LAMP levee issues.                                                                                              |
| Failure to complete due notice to Evonik/ Lonza Levee owners. Resistance to proposed floodplain mapping for unaccredited levee.                                                                  | Technical appeal and project delay. Request for full LAMP process  | FEMA R5 to resolve Mapleton Levee issues in advance of Flood Risk Review Meeting.                                                                                                                                                                                                                   |
| Resolution of Defenbaugh and Taylor-Chapman levee status and appropriate modeling and mapping                                                                                                    | Technical appeal and project delay. Request for full LAMP process  | Coordinate with RSC (STARR II) in resolving questions. Engage the community and levee owners in advance of the Flood Risk Review meeting to review levee status findings and proposed floodplain mapping. FEMA R5 engage RSC to resolve LAMP levee issues.                                          |



## Project Outreach and Communication Plan (POCP)

The CTP will work with the FEMA Regional Office during the initiation of this activity to develop the Project Outreach and Communication Plan (POCP) to support the implementation of the mapping project. The FEMA Regional Office will have access to many customizable outreach tools that have been developed for this process to support each touchpoint that the PMT has with the community.

The outreach and communication under this MAS will be focused on the coordination with FEMA R5 and the RSC in addressing questions and concerns regarding levees in the project area. A Flood Risk Review Meeting is already funded under MAS ISWS18-04.

**Standards:** All Community Engagement and Outreach work shall be performed in accordance with the standards specified in Section 5 – Standards. All communication with local governments will be done in accordance with 44 CFR Part 66.

**Deliverables:** The CTP shall deliver the following checked items to the FEMA Regional Project Officer in accordance with the schedule outlined in Section 6 – Schedule and include within the Technical Support Data Notebook (TSDN):

|                                     |                                                                                                                                                                                                                                                    |
|-------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <input checked="" type="checkbox"/> | A Project Communication Plan detailing outreach and coordination activities. NOTE: The MIP has tasks available to capture Outreach activities. Upon completion of these tasks, please upload relevant data to those tasks in the MIP. <sup>1</sup> |
| <input type="checkbox"/>            | Watershed/Community Assessment outputs, including logs of telephone discussions (if applicable)                                                                                                                                                    |
| <input type="checkbox"/>            | Meeting invitation, agenda, presentation slides (as requested), and meeting notes for FEMA review                                                                                                                                                  |
| <input type="checkbox"/>            | Action Identification and Advancement Plan (if applicable)                                                                                                                                                                                         |
| <input type="checkbox"/>            | Project update status reports for project communities                                                                                                                                                                                              |
| <input type="checkbox"/>            | Provide documentation of adherence with the requirements for the community 30-day review of proposed models and 30-day review of work maps, completed models, and associated information                                                           |

## Hydraulics Data Capture

*CTPs must complete this task in the MIP if an updated hydraulic analysis is completed. In addition, leveraged hydraulic data must be documented and submitted to the MIP for this task. Failure to submit this task when data should have been submitted is no longer an issue. The MIP redesign allows for tasks to be reopened so that data can be uploaded. If the CTP obtains hydraulic data that was not included in the MAS, the CTP shall contact the region to discuss the potential need for a change request to include the task and leverage as part of the award and request that this task be added to the MIP workflow.*

**Responsible Mapping Partner:** ISWS.

**Scope:** The CTP shall perform hydraulic analyses as described in Table 1.8: Summary of Hydraulic Analyses. Hydraulics analysis activities include establishing and reviewing regulatory floodways and

---

<sup>2</sup> You must sign into the CTP Collaboration Center to access this form. If you are not a registered user, please visit: <https://www.surveymonkey.com/r/CTPCollaborationCenterRegistration>

flood elevations for the 10 -, 4 -, 2 -, 1 -, “1- plus” and 0.2 percent annual chance events based on flood discharge rates computed under Develop Hydrologic Data. The hydraulic methods used for this analysis may include base level and/or enhanced level hydraulic modeling. The base level will use an automated hydraulic model and use the best available elevation data to model the 10-, 4-, 2-, 1-, “1- plus” and 0.2 percent annual chance events. It may not include field surveys, floodways, or mapped Base Flood Elevations (BFEs) but will include mapped A or AE zones per Table 1.8. The enhanced level may include field surveys, floodways, and the 10-, 4-, 2-, 1-, 1- plus and 0.2 percent annual chance events, using methods described in Table 1.8. The Mapping Partner, at a minimum, must delineate the floodplain and floodway, if applicable, boundaries of the base flood. The Mapping Partner must also delineate the floodplain boundaries associated with the 0.2-percent-annual-chance flood, if it is calculated.

### Exhibit 1.1 Hydraulic Analysis Options for Base and Enhanced Level Engineering

| Option | Cross Sections                                                                                                                                       | Flow Paths<br>(Left, Right<br>and Channel)                          | Manning’s “n”<br>Values                                                                               | Structures                                                                                                                                                                 | Flood Zone |
|--------|------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|
| A      | Auto-placed;<br>may be<br>unnaturally<br>straight with<br>computerized<br>look to them<br>adjusted or<br>auto-placed by<br>“intelligent”<br>methods. | Reach lengths<br>are assumed<br>equal.                              | Single value for<br>each cross<br>section.                                                            | Not included;<br>cross sections<br>placed as if<br>structures don’t<br>exist or cross<br>sections placed<br>appropriately<br>for structure<br>modeling.                    | A          |
| B      | Auto-placed<br>and hand<br>adjusted or<br>auto-placed by<br>“intelligent”<br>methods.                                                                | Reach lengths<br>computed by<br>offsetting<br>stream<br>centerline. | Overbanks<br>from Land Use<br>Land Cover<br>(LULC) data,<br>channel value<br>estimated<br>separately. | Not included;<br>but cross<br>sections placed<br>appropriately<br>for structure<br>modeling.                                                                               | A          |
| C      | Each section<br>reviewed by<br>engineers.                                                                                                            | Reach lengths<br>adjusted based<br>on draft<br>floodplain.          | Overbanks<br>LULC data,<br>channel value<br>estimated<br>separately.                                  | Included;<br>structure data<br>from national,<br>state or other<br>data source.<br>Estimated<br>based on<br>topography and<br>aerial photos<br>for those not<br>available. | A          |

| Option | Cross Sections                                                               | Flow Paths<br>(Left, Right<br>and Channel)        | Manning's "n"<br>Values                                                                                                    | Structures                                                                                                                            | Flood Zone |
|--------|------------------------------------------------------------------------------|---------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------|------------|
| D      | Each section reviewed by engineers.                                          | Reach lengths adjusted based on draft floodplain. | Overbanks from LULC data, channel value estimated separately and calibrated where possible.                                | Included; structure data from as-builts, design plans, "measured" in the field, or other community datasets with opening information. | A or AE    |
| E      | Each section reviewed by engineers, channel bathymetry included in sections. | Reach lengths adjusted based on draft floodplain. | Overbanks from LULC data and field data, channel value estimated separately from field data and calibrated where possible. | Included; structure data from field survey, as-builts, design plans, "measured" in the field.                                         | AE         |

The CTP shall use the cross-section and field data collected during Survey Data Capture and the topographic data collected during the Topographic Data Capture, when appropriate, to perform the hydraulic analyses. The hydraulic analyses will be used to establish flood water surface elevations, floodplain extents, and regulatory floodways for the listed study area or flooding sources.

If applicable, the CTP shall use the FEMA CHECK-2 or CHECK-RAS checking program to verify the reasonableness of the hydraulic analyses. To facilitate the independent QA/QC review, the CTP shall provide explanations for unresolved messages from the CHECK-2 or CHECK-RAS program, as appropriate. In addition, the CTP shall address all concerns or questions regarding the hydraulic analyses that are raised during the independent QA/QC review including resubmittal of deliverables as needed to pass the technical review.

The CTP shall document automated data processing and modeling algorithms for all GIS based studies and provide the data to FEMA for review to ensure these are consistent with the standards outlined above. If non-commercial (i.e., custom-developed) software is used for the analyses, then the CTP shall provide full user documentation, technical algorithm documentation, and software to FEMA for review before performing the hydraulic analyses.

Under MAS ISWS 18-04, the ISWS was contracted to restudy Kickapoo Creek. New hydrology was performed, resulting in flows doubling in the downstream area. As flows from Kickapoo Creek enter the vast Illinois River floodplain, they encounter numerous embankments (e.g., I-74 Interstate and the embankments at the Keystone Steel manufacturing facility). Traditional 1-D modeling funded under

MAS ISWS18-04 is not capable of accurately determining the complex flow paths and hydraulic impacts resulting from these embankments. A 2-D model is needed to reveal the effects of the embankments on the Kickapoo flow. Preliminary results indicate the embankments restrict, re-direct and split the flow as it makes its way to the Illinois River. With a better understanding of how the flow moves in this area due to the 2-D model results, 1-D models will be constructed to model the split flows in this area and used to present the modeling results on the workmaps to be presented at a Flood Risk Review Meeting.

Any flooding sources associated with a levee that are mapped as providing protection on effective FIRMs but will not meet certification requirements for the new FIRMs, will require revised hydraulic analysis. This revised analysis should be done in accordance with FEMA standards and guidance, as appropriate.

**Table 1.8: Summary of Hydraulic Analyses**

| Study Area/Flooding Source                           | Hydraulic Analysis Option *                              | Total Miles of New Base Level or Enhanced Level Hydraulics | Description of Level of study- i.e., AE with BFE or A zone mapping |
|------------------------------------------------------|----------------------------------------------------------|------------------------------------------------------------|--------------------------------------------------------------------|
| Kickapoo Creek at confluence with the Illinois River | 2-D model to inform 1-D final models under MAS ISWS18-04 | 2 miles of 1-D models                                      | Level B Zone A                                                     |

\*List Option letter from Exhibit 1.8 listed above.

Standards: All Hydraulic Data work shall be performed in accordance with the standards specified in Section 5 – Standards.

Deliverables: The CTP shall produce items listed in the Hydraulics Data Capture section within the most currently dated “Technical Reference: Data Capture” document, located at <https://www.fema.gov/media-library/assets/documents/34519>, made available to FEMA by uploading the digital data to the MIP in accordance with the schedule outlined in Section 6.

### **Independent QA/QC: Hydraulics Data Capture**

Responsible Mapping Partner: **ISWS**

Scope: The Independent QA/QC Mapping Partner shall perform an impartial review of the technical, scientific, and other information submitted by the CTP under Hydraulic Analysis to ensure that the data and modeling are consistent with FEMA standards, guidance, and standard engineering practice and are sufficient to revise the FIRM. FEMA may audit or assist in these activities if deemed to be necessary by the Regional Project Officer. This work shall include, at a minimum, the activities listed below.

Please note FEMA will also be performing periodic audits and overall study/project management to ensure study quality. The CTP will be responsible for addressing any and all comments resulting from independent QC, including resubmittal of deliverables as needed to pass technical review.

- Review the submittal for technical and regulatory adequacy, completeness of required information, and supporting data and documentation. The technical review is to focus on the following:
  - Use of acceptable model(s)
  - Use of appropriate methodology(ies)
  - Starting water-surface elevations
  - Cross-section geometry
  - Manning's "n" values and expansion/contraction coefficients
  - Bridge and culvert modeling
  - Ineffective and non-conveyance areas
  - Flood discharges
  - Regulatory floodway computation methods
  - Tie-in to upstream and downstream non-revised Flood Profiles and floodways
  - Agreement between the model, spatial data, work maps, Flood Profiles and Floodway Data Tables
  - Calibration of model(s), where high-water marks are available
  - Floodplain and floodway boundaries for the 1 percent and 0.2 percent annual chance events
- Verify that the data was submitted under the applicable GEOGRAPHIC FOOTPRINT folders in the MIP.
- Use the CHECK-2 or CHECK-RAS program, as appropriate, to flag potential problems and focus review efforts.
- Maintain records of all contacts, reviews, recommendations, and actions and make the data readily available to FEMA.
- Maintain an archive of all data submitted for hydraulic modeling review. (All supporting data must be retained for three years from the date a funding recipient submits its final expenditure report to FEMA, and once the study is effective all associated data should be submitted to the FEMA library).
- The reviewing Mapping Partner must document the results of the review in a memorandum or letter, send it to the Mapping Partner that performed the hydraulic analysis and post it to the MIP through the Independent QA/QC of Hydraulic Analyses task. The review document must present specific comments and may include any new calculations or model runs in support of the review.

Standards: All Independent QA/QC work shall be performed in accordance with the standards specified in Section 5 – Standards.

Deliverables: shall produce items listed in the Hydraulics Data Capture section within the most currently dated "Technical Reference: Data Capture" document, located at <https://www.fema.gov/media-library/assets/documents/34519>, made available to FEMA by uploading the digital data to the MIP in accordance with the schedule outlined in Section 6. Where paper documentation is required by state law for professional certifications, the CTP may submit the paper in addition to a scanned version of the paper for the digital record. Please coordinate with the regional and/or state representative to verify state reporting requirements.

- A Summary Report that describes the findings of the independent QA/QC review;
- Recommendations to resolve any problems that are identified during the independent QA/QC review.

## Floodplain Mapping Data Capture

***CTPs must complete this task in the MIP if a redelineation or digital conversion study is completed. A Floodplain Mapping MIP submittal is not required for revised data based on new or updated hydraulic or coastal analyses, as the required information shall be submitted with the Hydraulics Data Capture or Coastal Data Capture tasks. In addition, leveraged floodplain mapping data must be documented and submitted to the MIP for this task. Failure to submit this task when data should have been submitted is no longer an issue. The MIP redesign allows for tasks to be reopened so that data can be uploaded. If the CTP obtains floodplain mapping data that was not included in the MAS, the CTP shall contact the region to discuss the need to submit a change request to include the task and leverage as part of the award and request that this task be added to the MIP workflow.***

### **Responsible Mapping Partner: ISWS.**

The CTP shall perform floodplain mapping as described in Table 1.10: Summary of Floodplain Mapping. Floodplain Mapping activities include mapping and redelineation of the 1 percent and 0.2 percent annual chance event floodplains and regulatory floodways based upon updated topographic data.

The redelineation of floodplains utilizes updated topographic data to remap the floodplain boundary based upon effective water surface elevations. Per FEMA Standard ID #104, redelineation shall only be used when the terrain source data is better than effective, and the stream reach is classified as VALID in the CNMS database. Please review SID #104 listed in the last FEMA Policy for the most current language of the standard. Prior to redelineating effective floodplain boundaries, the current CNMS database should be reviewed to assess the appropriateness of this approach. The CTP shall use the effective FIS profile, floodway data table, FIRM/Flood Hazard Boundary Map (FHBM), and, as necessary, the effective hydraulic model, to delineate floodplain boundary on updated topography.

The 2012 LiDAR is better than the topographic data used to delineate the Illinois River Study in prior projects. However, an exception has been granted regarding the validity of the study. The Illinois River study from the USACE Upper Mississippi River Flow Frequency Study (UMRFFS) circa 2004 has been used for all DFIRM updates to counties bordering the Illinois River. The Illinois River crosses from east to west across the state draining 28,906 miles at the confluence with the Mississippi River. Although this study would no longer score as valid, no other alternative is available and incorporation into the Peoria DFIRM would provide continuity across the state until a full update of the Illinois River is performed.

**Table 1.10 Summary of Floodplain Mapping**

| Study Area/Flooding Source | Method        | Mapping Type (A/AE) | Miles | Topographic Data Source |
|----------------------------|---------------|---------------------|-------|-------------------------|
| Illinois River             | redelineation | AE                  | 46    | 2012 LiDAR              |

The CTP shall incorporate the results of all effective Letters of Map Change (LOMC) for all affected communities on the FIRM and provide to the appropriate PTS the required submittals for incorporation

into the National Flood Hazard Layer (NFHL). Also, the CTP shall address all concerns or questions regarding Floodplain Mapping that are raised during the independent QA/QC review.

Per FEMA Standard ID #134, if the redelineation topographic data indicates that the effective hydraulic analyses are no longer valid, further actions must be coordinated with the FEMA Project Officer and the CNMS database must be updated. Please refer to SID #134 listed in the last FEMA Policy for the most current language of the standard. The CTP shall capture flood hazard engineering and/or mapping data quality issues encountered during this activity in the CNMS database for the area(s) of interest. These issues will be entered as “Requests” or “Needs” in the CNMS requests feature dataset based on the nature of the deficiency encountered. Detailed information on performing this task can be found in the relevant standards specified in Section 5 – Standards.

Standards: All floodplain mapping work shall be performed in accordance with the standards specified in Section 5 – Standards. The CTP will perform self-certification audits for the Floodplain Boundary Standards for all flood hazard areas.

Deliverables: The CTP shall produce items listed in the Floodplain Mapping Data Capture section within the most currently dated “Technical Reference: Data Capture” document, located at <https://www.fema.gov/media-library/assets/documents/34519>, made available to FEMA by uploading the digital data to the MIP in accordance with the schedule outlined in Section 6.

## ***SECTION 2 – TECHNICAL AND ADMINISTRATIVE SUPPORT DATA SUBMITTAL***

**The Project Team members for this Flood Risk Project that have responsibilities for activities included in this MAS shall comply with the data submittal requirements summarized below and in appropriate guidance.**

All supporting documentation for the activities in this MAS shall be submitted according to FEMA standards and requirements and will include a FEDD folder. Submittals must be made to the appropriate PTS for a review of required materials. The CTP will respond to requests from FEMA or its contractors for additional information and ensure that all required documents are included in the TSDN.

If any issues arise that could affect the completion of an activity within the proposed scope or budget, the CTP shall complete and submit to FEMA a Special Problem Report (SPR) as soon as possible after the issue is identified. The SPR describes the issue and proposes possible resolutions. For additional information on SPRs, consult the FEMA Regional Office.

Information supporting FEMA standards and requirements regarding the TSDN and FEDD file may be found in the “Technical Reference: Data Capture” document and other associated guidance documents.

**Table 2.1: TSDN Section Mapping Activities**

| Mapping Activities              | TSDN Section          |                 |                        |                          |                        |                     |                      |                    |                               |                          |                  |                     |                         |
|---------------------------------|-----------------------|-----------------|------------------------|--------------------------|------------------------|---------------------|----------------------|--------------------|-------------------------------|--------------------------|------------------|---------------------|-------------------------|
|                                 | General Documentation | Change Requests | Telephone Conversation | Meeting Minutes/ Reports | General Correspondence | Hydrologic Analyses | Engineering Analyses | Hydraulic Analyses | Key to Cross-Section Labeling | Key to Transect Labeling | Draft FIS Report | Mapping Information | Miscellaneous Reference |
| Hydraulics Data Capture         |                       | X               | X                      | X                        | X                      | X                   | X                    | X                  | X                             | X                        | X                |                     | X                       |
| Floodplain Mapping Data Capture |                       | X               | X                      | X                        | X                      | X                   |                      | X                  | X                             | X                        |                  | X                   | X                       |

### ***SECTION 3 – PERIOD OF PERFORMANCE***

The mapping activities outlined in this MAS will be completed as specified in the Cooperative Agreement Funding Opportunity Announcement, Award Notice and/or Articles of Agreement. The Mapping Activities may be terminated at the option of FEMA or the CTP in accordance with the provisions of the Partnership Agreement dated **September 9, 2013**. If these mapping activities are terminated, all products produced to date must be submitted and updated into the MIP (if applicable) and the remaining funds, provided by FEMA for this MAS, from uncompleted activities will be returned to FEMA.

### ***SECTION 4 – FUNDING/LEVERAGE (For CTP, OFA, and/or Community)***

FEMA is providing funding, in the amount of **\$148,700** through a Cooperative Agreement to **Illinois State Water Survey** for the completion of this Flood Risk Project. During the discovery process, additional needs may be identified. Activities associated with any additional needs would be performed based on availability of additional funds. See Table 4.1.



Table 4.1: Contribution and Leverage

| TASK, PARTNER, COST and SCHEDULE                  |                          |                                        |                                      |                                                                   |                                                 |
|---------------------------------------------------|--------------------------|----------------------------------------|--------------------------------------|-------------------------------------------------------------------|-------------------------------------------------|
| <i>Project Task</i>                               | <i>FEMA Contribution</i> | <i>Partner Contribution (CTP Only)</i> | <i>Breakout Cost (if applicable)</i> | <i>% Partner (CTP Only) Leverage (of Total Project Task Cost)</i> | <i>Total Project Task Cost (FEMA + Partner)</i> |
| <b>Miscellaneous Tasks</b>                        |                          |                                        |                                      |                                                                   |                                                 |
| Project Management                                | \$14,241.00              | \$\$\$                                 | NA                                   | %                                                                 | \$14,241.00                                     |
| Project Risk ID & Mitigation                      | \$30,905.00              | \$\$\$                                 | NA                                   | %                                                                 | \$30,905.00                                     |
| Perform Community Engagement & Project Outreach   | \$14,229.00              | \$\$\$                                 | NA                                   | %                                                                 | \$14,229.00                                     |
| <b>Develop Regulatory Products &amp; Datasets</b> |                          |                                        |                                      |                                                                   |                                                 |
| Hydraulics Data Capture                           | \$64,008.00              | \$\$\$                                 | NA                                   | %                                                                 | \$64,008.00                                     |
| * Independent QA/QC: Hydraulics Data              | \$2,386                  | \$\$\$                                 | NA                                   | %                                                                 | \$2,386                                         |
| Floodplain Mapping: Redelineation Data Capture    | \$22,931.00              | \$\$\$                                 | NA                                   | %                                                                 | \$22,931.00                                     |
|                                                   | <b>\$148,700.00</b>      | <b>\$0.00</b>                          | <b>\$0.00</b>                        | <b>0%</b>                                                         | <b>\$148,700.00</b>                             |

## SECTION 5 – STANDARDS

The standards relevant to this MAS are presented in FEMA Policy 204-078-1 [Standards for Flood Risk Analysis and Mapping](http://www.fema.gov/media-library/assets/documents/35313), Revision 10, dated November 2019, located at <http://www.fema.gov/media-library/assets/documents/35313>. This Policy supersedes all previous standards included in the *Guidelines and Specifications for Flood Hazard Mapping Partners*, including all related appendices and Procedure Memorandums (PMs). Additional information and links to FEMA Technical References, guidance documents, templates and other resources may be accessed and downloaded at <http://www.fema.gov/guidelines-and-standards-flood-risk-analysis-and-mapping>. Revisions to the Policy memo are made on a regular basis. Some changes / updates are considered low impact, not requiring any scope, financial, process or technology changes to implement. CTPs should always check for the latest version of the policy memo to evaluate potential standards updates.

To facilitate the use of standards and related documents, users can access the FEMA *Guidelines and Standards Master Index* located here: [www.fema.gov/media-library/assets/documents/94095](http://www.fema.gov/media-library/assets/documents/94095). This index provides a cross-reference of documentation available for Flood Risk Projects, Letters of Map Change and related Risk MAP activities. The cross-referenced relationships are organized and accessible through

linkages for standards, guidance, technical references and templates. The master index is updated in coordination with the FEMA Policy Memo noted above.

CTPs and their sub-awardees must comply with FEMA's Federal Regulations in Chapter 44 of the Code of Federal Regulations (CFR), specifically CFR Parts 65, 66 and 67, and the appropriate year CTP Notice of Funding Opportunity and Agreement Articles. CTPs shall also coordinate with their Regional office to determine additional standards that should be met.

## ***SECTION 6 – SCHEDULE***

To accurately document Risk MAP activities, there are two tools available for identifying mapping activities as they align to the Mapping Information Platform (MIP). The activities documented in this MAS shall be completed in accordance with either Table 6.1 Project Activities Schedule or the Mapping Information Platform (MIP) MAS/SOW Workbook.<sup>2</sup>

Please work with your FEMA Region when submitting the MIP MAS/SOW Workbook or any other form that is representative of the information in Table 6.1. Table 6.1, the MIP MAS/SOW Workbook or a similar table is required and needs to be filled out and documented in this MAS as part of the grant's submission process.

---

<sup>2</sup> You must sign into the CTP Collaboration Center to access this form. If you are not a registered user, please visit: <https://www.surveymonkey.com/r/CTPCollaborationCenterRegistration>

**Table 6.1: Project Activities Schedule**

| <i>Project Task</i>                                        | <i>Baseline Start Date</i> | <i>Baseline End Date</i> |
|------------------------------------------------------------|----------------------------|--------------------------|
| <b>Miscellaneous Tasks</b>                                 |                            |                          |
| <b>Project Management</b>                                  | 09/01/2020                 | 08/31/2021               |
| <b>Project Risk ID &amp; Mitigation</b>                    | 09/01/2020                 | 08/31/2021               |
| <b>Perform Community Engagement &amp; Project Outreach</b> | 09/01/2020                 | 08/31/2021               |
| <b>Develop Regulatory Products &amp; Datasets</b>          |                            |                          |
| <b>Hydraulics Data Capture</b>                             | 09/01/2020                 | 06/30/2021               |
| <b>* Independent QA/QC: Hydraulics Data</b>                | 10/01/2020                 | 06/30/2021               |
| <b>Floodplain Mapping: Redelineation Data Capture</b>      | 09/01/2020                 | 06/30/2021               |

See R5\_MAS\_SOW worksheet tab 20-13\_Peoria

The CTP will coordinate with FEMA, or its designee, to develop a baseline schedule for individual project activities. FEMA or its designee will utilize the individual project task schedule create the Flood Risk Project in the MIP and baseline the project activities with schedule and cost information within 30 days of the funds being awarded and FEMA’s approval of the final cost and schedule. The baseline schedule for individual project activities may be re-baselined in the MIP with approval from the FEMA Project Officer, and does not require a change to this MAS unless the overall project end date is modified.

## ***SECTION 7 – CERTIFICATIONS***

### **Data Capture**

- **Data Capture:** Please refer to the current “Technical Reference: Data Capture” document, located at <https://www.fema.gov/media-library/assets/documents/34519>, for instructions on certifications. Generally, each Data Capture task includes certification forms and a project narrative. Mapping Partners should complete and submit only one Certification of Completeness and/or one Certification of Compliance form when the task is complete.

### **Develop Hydrologic Data, Develop Hydraulic Data, Perform Coastal Analysis, and Perform Floodplain Mapping**

- A Registered Professional Engineer shall certify hydrologic and hydraulic and coastal analyses and data in accordance with 44 CFR 65.6(f).
- Any levee systems to be accredited will be certified by the levee owner or other appropriate entity in accordance with 44 CFR 65.10.
- Certifications are required at the time the intermediate or final data is submitted.

## ***SECTION 8 – TECHNICAL ASSISTANCE AND RESOURCES***

Project Team members may obtain copies of FEMA-issued LOMCs, archived engineering backup data, and data collected as part of the CNMS process from FEMA and/or your Regional Project Officer.

General technical and programmatic information can be downloaded from the FEMA website at <https://www.fema.gov/cooperating-technical-partners-program>. Specific technical and programmatic support may be provided through FEMA and/or its contractor; such assistance should be requested through the FEMA Project Officer specified in Section 12 – Points of Contact.

Project Team members also may consult with the FEMA Regional Project Officer to request support in the areas of selection of data sources, digital data accuracy standards, assessment of vertical data accuracy, data collection methods or subcontractors, and GIS-based engineering and modeling training.

Please contact the region to obtain the most recent version of the Risk MAP timeline.

Assistance with the MIP may be requested at [miphelp@RiskMAPcds.com](mailto:miphelp@RiskMAPcds.com).

## ***SECTION 9 – CONTRACTORS***

The CTP does not intend to use the services of a contractor for this SOW. No transfer of funds to agencies other than those identified in the approved cooperative agreement application shall be made without prior approval from FEMA. The CTP shall ensure that the procurement for all contractors, if any are used for this SOW, complies with the requirements of 2 CFR Part 200.

Guidance provided in this part includes, but is not limited to, contract administration and recordkeeping, notification requirements, review procedures, competition, methods of procurement, and cost and pricing analysis. The 2 CFR 200 documents may be viewed online at <http://www.ecfr.gov/cgi-bin/text-idx?SID=cc011f4fb962e68cb0da4bc91e8fbb43&mc=true&node=pt2.1.200&rgn=div5>. Additionally, contractors must not pose a conflict of interest issue.

## SECTION 10 – REPORTING

**Financial Reporting:** Because funding has been provided to the CTP by FEMA, financial reporting requirements for the CTP will be in accordance with the terms of the Cooperative Agreement Funding Opportunity Announcement, Articles of Agreement or Award Notice for this MAS. The CTP shall also refer to 2 CFR Part 200. **ISWS through the University of Illinois shall provide financial reports to the FEMA Regional Project Officer and Assistance Officer in accordance with the terms of the signed Cooperative Agreement for this MAS.**

**Performance Reporting:** Recipients are responsible for providing a signed performance report using the required list of information shown in the NOFO (or old SF-PPR if you prefer) on a quarterly basis throughout the period of performance, including partial calendar quarters as well as for periods where no grant award activity occurs. The CTP shall refer to 2 CFR Part 200 to obtain minimum requirements for progress reporting. The Project Officer, as needed, may request additional information on progress.

The CTP may meet with FEMA and/or its contractor(s) as frequently as needed to review the progress of the project in addition to the quarterly financial and status submittals. These meetings may alternate between FEMA’s Regional Office, the **ISWS** office, and conference calls, as necessary.

The CTP must report performance of the grant in conjunction with the progress reporting. The performance of the CTP is measured by the following criteria. Quantitative Targets for performance measures will be defined using the *FY2020 DHS NOFO for CTPs Appendix D Performance Measure References*, “*CTP Performance Measures Matrix* in conjunction with your FEMA PM and defined in Table 10.1.

**Table 10.1: Performance Measures Targets**

**See CTP\_Metrics\_2020. xlsx for Summary of Performance Measures Targets**

| Output Measurement Options                                                                                                                                                                                                                                                                                                                                                                                                       | Recorded Metric Unit/Scale                                                                                                                        | Peoria Data Development Additional Tasks |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------|
|                                                                                                                                                                                                                                                                                                                                                                                                                                  |                                                                                                                                                   | ISWS20-13                                |
| 1. Net NVUE mileage                                                                                                                                                                                                                                                                                                                                                                                                              | # of Miles (Initiated)                                                                                                                            | 2 miles new Zone A                       |
| 0.92 to 1.08                                                                                                                                                                                                                                                                                                                                                                                                                     | SPI score (EV/planned value)<br>CPI score (EV/actual cost)                                                                                        | 0.92 to 1.08                             |
| 1. Grant amendments that are not outside the CTPs span of control will be evaluated and documented.<br>2. Excessive CRs that are due to project management issues within the CTP’s control will require additional discussion and possible development of a quality performance plan to identify a continued path to improved project and program management.<br>3. Reporting within specified timelines throughout the project. | # of CRs<br>0=no CRs<br>1=amendment needed outside of control<br>2=amendment needed within control<br>3=multiple amendments needed within control | Goal: 0                                  |

|                                                                                                                                                                                                                      |                         |                                    |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|------------------------------------|
| Monthly updates for all cases, including (%) of active tasks per                                                                                                                                                     | Achieved / Not achieved | Monthly MIP update                 |
| 2. Ongoing and regular coordination with other state/local offices to discuss agency's prioritization process for Risk MAP projects as well as schedules, meetings, strategy development and stakeholder engagement. | Achieved / Not achieved | Monthly calls with FEMA & IDNR/OWR |

The CTP shall communicate with communities throughout the life of each project. Continued engagement is necessary and appropriate and will build upon the relationships established or enhanced during Discovery and provide transparency into the Risk MAP process. This may occur through monthly or quarterly updates or project status calls with community leaders, project websites including updates at several milestones or along a specific timeline, or other methods.

## ***SECTION 11 – PROJECT COORDINATION***

Throughout the project, all members of the Project Team will coordinate, as necessary, to ensure the products meet the technical and format specifications required and contain accurate, up-to-date information. Coordination activities may include:

- Meetings, teleconferences, and/or video conferences with FEMA and other Project Team members **will be conducted as per the communication plan.**
- Telephone conversations with FEMA and other Project Team members on a **monthly** basis, and an ad hoc basis, as required.
- Updates to the MIP and other FEMA status information systems in accordance with FEMA standards and requirements.
- E-mail, facsimile transmissions, and letters, as required.

## ***SECTION 12 – PROTECTION OF PRIVACY INFORMATION***

To accomplish the tasks outlined in this scope, FEMA will provide the CTP access to Risk Analysis Management (RAM) which includes all PII collected in RAM as outlined in DHS/FEMA/PIA-045 Hazard Mitigation Planning and Flood Mapping Products and Services Support Systems.  
<https://www.dhs.gov/publication/dhsfemapia-045-hazard-mitigation-planning-and-flood-mapping-products-and-services>

The information sharing outlined in this scope authorized by the following System of Records Notice(s) and Routine Use(s): DHS/FEMA-014 Hazard Mitigation Planning and Flood Mapping Products and Services Records System of Records. <https://www.federalregister.gov/documents/2017/10/25/2017-23205/privacy-act-of-1974-system-of-records>

When necessary to accomplish a function related to this system of records, CTPs (term used to include any subrecipients and/or contractors used by the CTP for this work) must comply with the Privacy Act.

Individuals provided information under this routine use are subject to the same Privacy Act requirements and limitations on disclosure as are applicable to DHS officers and employees.

The mapping program for the NFIP, implemented through Risk MAP, is established through the National Flood Insurance Act of 1968, as amended and the Biggert-Waters Flood Insurance Reform Act of 2012 (BW-12), as amended (42 U.S.C. 4001 et seq.). The mapping program is governed by the implementing regulations at Code of Federal Regulations - Title 44 (44 CFR) parts 59-72.

The CTP will limit access to the PII provided by FEMA under this contract only to the CTP's authorized personnel who need to know the information to accomplish the tasks outlined in this contract.

Definition. As used in this section, "personally identifiable information" means information that can be used to distinguish or trace an individual's identity, either alone or when combined with other information that is linked or linkable to a specific individual. (See Office of Management and Budget (OMB) Circular A-130, Managing Federal Information as a Strategic Resource).

- A. The CTP will ensure that initial privacy training, and annual privacy training, thereafter, is completed by CTP employees, subrecipients and/or contractors and subcontractors who
  - i. Have access to a system of records.
  - ii. Create, collect, use, process, store, maintain, disseminate, disclose, dispose, or otherwise handle personally identifiable information on behalf of an agency; or
  - iii. Design, develop, maintain, or operate a system of records
- B. FEMA will provide the link to external facing initial privacy training, and annual privacy training thereafter, to CTPs for the duration of this grant.
- C. The CTP shall maintain and, upon request, provide documentation of completion of privacy training to FEMA.
- D. The CTP shall not allow any employee access to a system of records, or permit any employee to create, collect, use, process, store, maintain, disseminate, disclose, dispose or otherwise handle personally identifiable information, or to design, develop, maintain, or operate a system of records unless the employee has completed privacy training, as required by this section.


The CTP will ensure no computer matching, as that term is defined in U.S.C. § 552a(o), will occur for the purpose of establishing or verifying eligibility or compliance as it relates to cash or in-kind assistance of payments under federal benefit programs.

If at any time during the term of this cooperative agreement any part of FEMA PII, in any form, that the CTP obtains from FEMA ceases to be required by the CTP for the performance of the scope, or upon termination of the cooperative agreement, whichever occurs first, the CTP shall, within fourteen (14) days thereafter, promptly notify FEMA and securely return PII to FEMA, or, at FEMA's written request destroy, un-install and/or remove all copies of such PII in the CTP's possession or control, and certify in writing to FEMA that such tasks have been completed.

## SECTION 13 – POINTS OF CONTACT

The points of contact for this Flood Risk Project are **John Wethington**, the FEMA Regional Project Officer; **Sally McConkey**, the Project Manager for **ISWS**; or subsequent personnel of comparable experience who are appointed to fulfill these responsibilities. When necessary, any additional FEMA assistance should be requested through the FEMA Regional Project Officer.

Each party has caused this MAS to be executed by its duly authorized representative.



08/10/2020

---

**Sally McConkey**  
Project Manager

Date

---

**John Wethington**  
Regional Project Officer  
Federal Emergency Management Agency, Region 5

Date

---

Julia McCarthy  
Risk Analysis Branch Chief  
Federal Emergency Management Agency, Region 5

Date

---

Mary Beth Caruso  
Mitigation Division Director  
Federal Emergency Management Agency, Region 5

Date