

FFY2020 MAS Portfolio Summary

Overview

The FFY2020 CHAMP portfolio contains **14 documents** covering 13 flood risk project MASs plus 1 Program Management SOW. The portfolio spans three broad categories: (1) **completion/post-preliminary processing** for counties already through data development (Clay, Effingham, Cook/Kane); (2) **new Data Development** studies building H&H models to KDP-2 but explicitly requiring separate future MAS grants before DFIRM production (Bureau, Johnson, Massac, Pope, Wayne-Skillet, Kishwaukee, and supplemental work for Peoria); and (3) **targeted continuation/engagement** projects resolving specific technical blockers before a study can advance (Rock River – East Moline levee, Turtle Creek – bi-state hydraulic model). A statewide LOMR Review Partners MAS rounds out the portfolio.

All documents are dated June 2020 and reference the CTP Partnership Agreement of September 9, 2013. The Cooperative Agreement period for FY20 grants is not explicitly stated in most MASs (they defer to Award Notice terms); only the LOMR MAS specifies an end date of **June 30, 2022**.

Estimated total FEMA funding across all 14 documents: ~\$5,711,212

MAS	Location	FEMA Funding
ISWS_20-01 (PM)	Statewide IL	\$70,000
ISWS_20-02	Clay County	\$172,500
ISWS_20-03	Effingham County	\$195,500
ISWS_20-04	Cook & Kane Counties	\$311,000
ISWS_20-05	Rock River (Rock Island/Henry/Whiteside)	\$60,400
ISWS_20-06	Turtle Creek (Winnebago/Rock County WI)	\$144,100
ISWS_20-07	Bureau County	\$798,100
ISWS_20-08	Johnson County	\$786,900
ISWS_20-09	Massac County	\$793,600
ISWS_20-10	Pope County	\$297,500
ISWS_20-11	Wayne County (Skillet HUC8)	\$190,700
ISWS_20-12	Kishwaukee HUC8	\$1,370,472
ISWS_20-13	Peoria County	\$148,700
ISWS_20_LOMR	Statewide IL	\$371,740
TOTAL		\$5,711,212

Projects

ISWS_20-01: Statewide Program Management SOW

- **Activity Type:** Program Management (PM SOW) — not a flood risk mapping project; cannot result in FIRM production
- **Phase:** Annual PM activities for FFY2020 grant cycle
- **Scope:** ISWS will prepare a joint State Business Plan with IDNR/OWR documenting capabilities, accomplishments, and flood hazard mapping needs for Illinois. Global Program Management activities cover integration of all active CHAMP projects, quarterly risk assessments, earned value monitoring in the MIP, and continuing education/certification maintenance (CFM, PE, GISP, AICP) for CHAMP staff. Global Outreach for Mapping supplements project-specific community engagement and promotes NFIP flood mapping awareness statewide.
- **Deliverables:** Joint Illinois Business Plan (with PM Plan integrated), quarterly project risk assessment updates and CTP Performance Metrics in ND Grants quarterly reports, outreach activities
- **Period:** Per Cooperative Agreement Award Notice (FFY2020; no explicit calendar dates stated beyond award period)
- **Budget:** \$70,000 (FEMA)
- **Multi-year:** Yes — PM SOW is issued every grant year as a standing requirement; Business Plan explicitly feeds future funding eligibility
- **Recommended Next Steps:** Submit Business Plan to FEMA Region V; incorporate any updated CNMS mapping needs; maintain PM plan and risk registers for all active FY20 MASs throughout grant period

ISWS_20-02: Clay County Countywide Digital FIRM — Continued & Post Preliminary Processing

- **Activity Type:** Countywide Digital FIRM — Preliminary Production & Post-Preliminary Processing (PPP)
- **Phase:** Completion phase — Produces Preliminary Products (QR3/KDP-3), then Distribution, Due Process, and Final Mapping. Continuation of ISWS17-03 (extension & rescope), which funded data development and earlier QR steps.
- **Scope:** This MAS funds the remaining Produce Preliminary Products tasks (Dated QR3 and KDP 3) that were not included under the preceding MAS ISWS17-03. It also covers Distribution of Preliminary Products to all affected communities, Due Process Management (appeals, protests, statutory notifications), and Final Mapping Products Management for a countywide digital FIRM for Clay County, IL.
- **Deliverables:** Preliminary FIRM/FIS for Clay County (passed QR3/KDP-3), community distribution packages, due process documentation, Final FIRM/FIS database submitted to MIP (QR5 and Final Mapping Products Data Capture)
- **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
- **Budget:** \$172,500 (FEMA)
- **Multi-year:** Yes — explicitly a continuation of ISWS17-03 (FFY2017 grant). This MAS is the final production phase; if successful, no further MAS needed for Clay County DFIRM.

- **Recommended Next Steps:** Complete QR3 and KDP-3 submission; issue Preliminary FIRM; conduct community meetings/appeals period; resolve any protests; submit Final Mapping Products for effective FIRM publication via FEMA Letter of Final Determination (LFD) and 6-month compliance period
-

ISWS_20-03: Effingham County Countywide Digital FIRM — Continued & Post Preliminary Processing

- **Activity Type:** Countywide Digital FIRM — Preliminary Production & Post-Preliminary Processing (PPP)
 - **Phase:** Completion phase — same structure as ISWS_20-02. Continuation of ISWS17-03.
 - **Scope:** This MAS funds the remaining Produce Preliminary Products tasks (Dated QR3 and KDP 3) not included under ISWS17-03 for Effingham County, IL. It also includes Distribution of Preliminary Products, Due Process Management, and Final Mapping Products Management. The project is a countywide digital FIRM conversion, updating all regulated flood zones for Effingham County.
 - **Deliverables:** Preliminary FIRM/FIS for Effingham County (passed QR3/KDP-3), community distribution packages, due process documentation, Final FIRM/FIS database; Produce Preliminary Map Products milestone
 - **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$195,500 (FEMA)
 - **Multi-year:** Yes — continuation of ISWS17-03 (FFY2017 grant). Completion MAS; no further technical phases anticipated for the core countywide study.
 - **Recommended Next Steps:** Same as Clay: complete QR3/KDP-3, issue Preliminary FIRM, run due process, resolve any appeals, submit Final Mapping Products for LFD and effective FIRM
-

ISWS_20-04: Cook & Kane Counties PMR — QR3-Eff Digital FIRM Continued & Post Preliminary Processing

- **Activity Type:** Physical Map Revision (PMR) — Preliminary Production & Post-Preliminary Processing (PPP) for Spring Creek and Poplar Creek Watersheds
- **Phase:** Completion phase — Produces Preliminary Products (QR3/KDP-3), then Distribution, Due Process, and Final Mapping. Continuation of ISWS19-10 (FFY2019).
- **Scope:** This MAS funds the remaining Produce Preliminary Products tasks (Dated QR3 and KDP 3) not included under ISWS19-10 for the Spring and Poplar Creek Watersheds in portions of Cook County and Kane County, IL. It also covers Preliminary Distribution, Due Process Management, and Final Mapping Products Management. The MAS notes a risk from in-process PMRs in Cook County that could affect schedule.
- **Deliverables:** Preliminary FIRM panels for Spring/Poplar Creek areas in Cook & Kane Counties (QR3/KDP-3 passed), community distribution, due process documentation, Final Mapping Products; Technical Support Data Notebook (TSDN)
- **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
- **Budget:** \$311,000 (FEMA)
- **Multi-year:** Yes — continuation of ISWS19-10 (FFY2019). Completion MAS for this PMR; active Cook County in-process PMRs noted as a schedule risk.

- **Recommended Next Steps:** Complete QR3/KDP-3; coordinate with Cook County PMR submitters to avoid conflicts; issue Preliminary; conduct community meetings; resolve appeals; submit Final Mapping Products for effective FIRM
-

ISWS_20-05: Lower Rock River HUC8 — Continued Community Engagement

- **Activity Type:** Community Engagement / Project Outreach (not H&H production); Data capture limited to integrating RSC-prepared work maps
 - **Phase:** Late engagement phase — Study H&H completed previously; FRR meeting pending under ISWS17-06. This MAS resolves a specific outstanding mapping question (East Moline levee area west of IL Route 5/92) before FRR can finalize work maps.
 - **Scope:** A Rock River floodplain analysis was completed in 2014 and refined under ISWS17-06 (re-engagement, Meredosia Ditch study, PMR models). IDNR/OWR issued a letter of concurrence April 17, 2020. An issue arose: flood waters from the Rock River may extend west of IL Route 5/92 into areas protected by East Moline levees (accredited against Mississippi River/Sugar Creek), which had not been fully evaluated. ISWS coordinates with FEMA and STARR II to evaluate this question and integrate RSC-prepared mapping west of IL Route 5/92 into work maps, to be presented at the FRR meeting planned for autumn 2020 (funded under ISWS17-06).
 - **Deliverables:** Updated work maps incorporating RSC-prepared flood hazard mapping west of IL Route 5/92; integration into FRR meeting materials; future watershed phases identified for future funding
 - **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$60,400 (FEMA)
 - **Multi-year:** Yes — this is the 3rd generation of Rock River work (2014 original → ISWS17-06 → ISWS20-05). After FRR, additional MASs for multiple watershed phases (Henry, Rock Island, Whiteside PMR development) are anticipated for future funding.
 - **Recommended Next Steps:** Resolve East Moline/IL Route 5/92 flood mapping issue with FEMA/RSC; update work maps; hold FRR meeting (funded under ISWS17-06, autumn 2020); then scope future PMR MASs for full lower Rock River DFIRM update
-

ISWS_20-06: Turtle Creek — Resolution of Bi-State H&H and Mapping

- **Activity Type:** Hydraulic Data Development (bi-state H&H model resolution) + FRR Meeting
- **Phase:** Technical resolution phase — Study has been ongoing since ISWS15-04 (FFY2015) and ISWS17-05 (FFY2017). This MAS resolves outstanding bi-state modeling disputes before workmaps and FRR can proceed.
- **Scope:** A WDNR 2012 study covered a 1-mile IL reach of Turtle Creek near the IL/WI state line. ISWS15-04 updated the IL reach model; ISWS17-05 attempted to incorporate Fehr Graham's newer community-submitted model but revealed significant upstream impacts extending ~3 miles into Wisconsin. A Nov. 7, 2019 FEMA/ISWS/IDNR-OWR/WDNR meeting identified multiple outstanding issues (railroad embankment treatment, zero-rise vs. floodway-standard differences between states, cross-section truncation). This MAS tasks ISWS to develop a single hydraulic model acceptable to both states, prepare draft work maps spanning IL and WI, resolve floodway, and hold a Flood Risk Review meeting with all stakeholders.

- **Deliverables:** Resolved bi-state hydraulic model; floodway analysis (single model or two-state models); draft work maps; FRR meeting convened; post-FRR documentation; Illinois and Wisconsin regulatory submittals
 - **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$144,100 (FEMA)
 - **Multi-year:** Yes — 3rd generation (ISWS15-04 → ISWS17-05 → ISWS20-06). After model resolution and FRR, a future MAS will be needed to produce and issue Preliminary FIRM panels and complete post-preliminary processing for both states.
 - **Recommended Next Steps:** Complete bi-state hydraulic model; hold FRR meeting with IL and WI stakeholders; after model acceptance by IDNR-OWR and WDNR, scope a Preliminary/PPP MAS for both states' FIRM panels
-

ISWS_20-07: Bureau County Data Development

- **Activity Type:** Hydrologic & Hydraulic Data Development (Zone A studies) — ending at KDP-2
 - **Phase:** Phase 1 (Data Development only) — No prior Discovery or data development for Bureau County within these HUC8 watersheds. Future MAS required for KDP-3 through Final FIRM.
 - **Scope:** This MAS produces H&H studies for CNMS unverified Zone A streams in Bureau County (portions of Spoon, Green, and Lower Illinois-Senachwine Lake HUC8 watersheds). Key study areas include: ~14.9 miles of Green River within Bureau County (plus upstream/downstream reaches in Henry, Whiteside, and Lee Counties for model tie-in); ~5 miles of Big Bureau Creek (Zone AE without floodway), ~1 mile of West Bureau Creek, and ~5 miles of Hennepin Canal near Tiskilwa. A prior STARR II Tiskilwa Levee LAMP study is incorporated and extended. A constricted-vs-natural-valley analysis of Tiskilwa Levee is included for workmap delineation. Illinois River floodplain continuity addressed via USACE UMRFFS circa 2004.
 - **Deliverables:** Hydrologic and hydraulic study reports; H&H models; work maps to KDP-2; Technical Support Data Notebook (TSDN)
 - **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$798,100 (FEMA)
 - **Multi-year:** Yes — explicitly states "Future mapping updates (under separate future funding) will incorporate the results of these studies in the DFIRM." Additional MAS(s) needed for KDP-3 (Produce Preliminary), distribution, due process, and Final Mapping.
 - **Recommended Next Steps:** Complete H&H models and workmaps; submit at KDP-2; then scope a new MAS for DFIRM production (QR3/KDP-3 through Final Mapping); consider whether Green River coordination across Lee/Whiteside/Henry Counties warrants a broader watershed MAS
-

ISWS_20-08: Johnson County Data Development

- **Activity Type:** Hydrologic & Hydraulic Data Development — ending at KDP-2
- **Phase:** Phase 1 (Data Development only) — No prior Discovery or data development in Johnson County. Future MAS required for countywide DFIRM.
- **Scope:** This MAS supports a future countywide DFIRM for Johnson County. Studies are being undertaken for all CNMS unverified stream miles within the county across five HUC8 watersheds (Big Muddy, Saline, Lower Ohio, Lower Ohio-Bay, Cache). Key tasks include Zone A updates, new unmapped Zone A studies, and updated

Zone AE analysis along ~1.9 miles of Little Cache Creek through Vienna (including field survey). The Cache River is upgraded from Zone A16 to Zone AE to align with adjacent Pulaski County. Levees (Karnak Levee, Cache River Levee System) are a major consideration — the Karnak Levee is scheduled for repairs changing open-flow conditions between Upper and Lower Cache Rivers requiring 2D HEC-RAS modeling. Ohio River redelineation using updated topography is included.

- **Deliverables:** Hydrologic and hydraulic study reports; H&H models (including 2D HEC-RAS for Cache River); field survey data; work maps to KDP-2; TSDN
 - **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$786,900 (FEMA)
 - **Multi-year:** Yes — explicitly states "separate future funding" needed for countywide DFIRM. Future MAS(s) needed for KDP-3 through Final FIRM.
 - **Recommended Next Steps:** Complete H&H models including 2D Cache River model coordinated with Karnak Levee repair schedule; coordinate with Kentucky Division of Water on Ohio River boundary conditions; submit at KDP-2; scope future DFIRM production MAS for Johnson County
-

ISWS_20-09: Massac County Data Development

- **Activity Type:** Hydrologic & Hydraulic Data Development — ending at KDP-2
 - **Phase:** Phase 1 (Data Development only) — No prior Discovery or data development for Massac County. Future MAS required for countywide DFIRM.
 - **Scope:** This MAS supports a future countywide DFIRM for Massac County. Studies update all unverified Zone A and Zone AE miles and re-delineate Ohio River miles within Massac County (Lower Ohio HUC8). IDNR-OWR has specifically requested an update to Massac Creek (~11.3 miles, Zone AE) near Metropolis. Ohio River re-delineation uses the effective USACE hydrology (Ohio River Basin Comprehensive Survey, 1966) with datum conversion from NGVD29 to NAVD88. The Brookport Levee System and Reevesville Levee System influence hydraulics significantly. Kentucky Division of Water has completed digital FIRM products for the Ohio River on the Kentucky side; this MAS coordinates with those products. Highly braided/interconnected ditches and complex topography require 2D HEC-RAS.
 - **Deliverables:** H&H models including Ohio River redelineation; Zone A and AE studies; work maps to KDP-2; TSDN; datum conversion documentation
 - **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$793,600 (FEMA)
 - **Multi-year:** Yes — explicitly states "separate future funding" needed for countywide DFIRM. Future MAS(s) needed for KDP-3 through Final FIRM.
 - **Recommended Next Steps:** Complete H&H models including Ohio River redelineation and Massac Creek Zone AE upgrade; coordinate with Kentucky Division of Water; submit at KDP-2; scope future Massac/Pope combined or individual DFIRM production MAS
-

ISWS_20-10: Pope County Data Development

- **Activity Type:** Hydrologic & Hydraulic Data Development — ending at KDP-2

- **Phase:** Phase 1 (Data Development only) — No prior Discovery or data development for Pope County. Future MAS required for countywide DFIRM.
 - **Scope:** This MAS supports a future countywide DFIRM for Pope County. Studies update all unverified Zone A miles and re-delineate Ohio River BFEs within Pope County (Lower Ohio, Lower Ohio-Bay, and Saline HUC8s). No effective Zone AE streams exist in Pope County (aside from the Ohio River), so no Zone A-to-AE upgrades are planned. Ohio River re-delineation uses 1966 USACE hydrology with NGVD29-to-NAVD88 datum conversion. The Golconda Levee System and Reevesville Levee System are significant influences. This study is coordinated with the adjacent Massac County study (ISWS_20-09). Kentucky Division of Water FIRM coordination is required for Ohio River boundary conditions. Multiple streams (Bay Creek, Lusk Creek Zone A16) are studied with coordinate-initiated discussion on Zone AE treatment.
 - **Deliverables:** H&H models; Ohio River redelineation; Zone A studies; work maps to KDP-2; TSDN
 - **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$297,500 (FEMA)
 - **Multi-year:** Yes — explicitly states "separate future funding" for countywide DFIRM. KDP-3 through Final FIRM requires a future MAS.
 - **Recommended Next Steps:** Complete H&H models and Ohio River redelineation in coordination with Massac County study; coordinate with Kentucky Division of Water; submit at KDP-2; consider joint Pope/Massac DFIRM production MAS for efficiency
-

ISWS_20-11: Wayne County (Skillet HUC8) Data Development

- **Activity Type:** Hydrologic & Hydraulic Data Development (Zone A studies, BLE-B and BLE-C) — ending at KDP-2
 - **Phase:** Phase 1 (Data Development only) for the western/Skillet portion of Wayne County. Complements ISWS MAS17-03 (Little Wabash Data Development), which covered the eastern portion of Wayne County. No prior Discovery or data development in the Skillet HUC8 portion.
 - **Scope:** This MAS covers the western portion of Wayne County (Skillet Fork HUC8, 05120115), updating all CNMS unverified Zone A miles. BLE-B level studies for Skillet Fork tributaries and BLE-C level study for main-stem Skillet Fork. Study extents extend into Marion County (upstream to USGS 03380350) and White County (downstream to USGS 03381000) for model tie-in. Community officials from Fairfield and Wayne City were briefed at the Little Wabash Watershed FRR meeting (Feb. 20, 2020). Multiple levees identified (Fish Slough Creek, Dry Fork, Skillet Fork Drainage Ditch, unnamed levees); levee outreach and LAMP analysis deferred to FEMA/RSC (STARR II).
 - **Deliverables:** H&H models (BLE-B/BLE-C); Zone A studies; work maps to KDP-2; TSDN
 - **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$190,700 (FEMA)
 - **Multi-year:** Yes — explicitly states "separate future funding" needed for countywide DFIRM. Future MAS(s) needed for KDP-3 through Final FIRM. Wayne County will need a combined Skillet + Little Wabash DFIRM production MAS to complete the countywide update.
 - **Recommended Next Steps:** Complete BLE-B/C H&H models; submit at KDP-2; coordinate with FEMA/RSC on levee LAMP resolution for Skillet levees; then scope a combined Wayne County (Skillet + Little Wabash) DFIRM production MAS
-

ISWS_20-12: Kishwaukee HUC8 Watershed Data Development (Phase 1)

- **Activity Type:** Hydrologic & Hydraulic Data Development (multi-phase watershed approach) — ending at KDP-2 for Phase 1
 - **Phase:** Phase 1 of an explicitly described multi-year (4+ MAS grants) phased study. Discovery was performed under MAS17-02. This is the first data development phase.
 - **Scope:** This MAS initiates a multi-year, phased H&H data development program for the entire Kishwaukee HUC8 watershed (07090006). Phase 1 focuses on the 15-mile main-stem Kishwaukee River reach within Winnebago County, including: full hydrologic analysis for the entire main-stem; field surveys of structures and channel cross sections within Winnebago County; hydraulic analysis of the Winnebago County reach (~15 miles, BLE-D); and surveys for scoped Zone AE tributaries in contributing HUC-10 watersheds (Kishwaukee River HUC10, Killbuck Creek HUC10, South Branch Kishwaukee HUC10). Later phases will proceed upstream through Boone County and McHenry County, working upstream as each main-stem confluence is ready to provide boundary conditions for the next tributary study.
 - **Deliverables:** Full watershed hydrologic analysis; H&H models for Winnebago County Kishwaukee reach; field survey data; tributary survey data; work maps to KDP-2; TSDN
 - **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$1,370,472 (FEMA) — largest single flood risk project in the FY20 portfolio
 - **Multi-year:** Yes — explicitly stated as Phase 1 of a "potentially four or more separate MAS grants" multi-year effort. DFIRM updates will be "funded in future grants." Future phases needed for Boone County, McHenry County, and remaining HUC-10 tributaries; DFIRM production MAS needed after all phases complete.
 - **Recommended Next Steps:** Complete Phase 1 H&H modeling and surveys; submit at KDP-2; plan Phase 2 (Boone County main-stem + contributing HUC-10s) for FFY2021 or FFY2022 grant cycle; ultimately 4+ additional MASs anticipated before final DFIRM can be produced
-

ISWS_20-13: Peoria County Data Development — Additional Tasks

- **Activity Type:** Hydrologic & Hydraulic Data Development (supplemental tasks) + Floodplain Redelineation — advancing to KDP-3 / QR3
- **Phase:** 5th generation of Peoria County DFIRM project (ISWS11-16 → ISWS12-05 → ISWS13-05 → ISWS18-04 → ISWS20-13). This MAS funds three specific unresolved tasks blocking advancement from ISWS18-04 to QR3.
- **Scope:** Three specific tasks blocking QR3 are addressed: (1) **Kickapoo Creek Embankments 2D Modeling** — Traditional 1D modeling from ISWS18-04 cannot handle complex split-flow embankments (I-74, Keystone Steel); a 2D HEC-RAS model is needed to reveal flow paths, followed by revised 1D models and approximately 1–2 additional BLE-B Zone A miles; (2) **Levee Risk Identification and Mitigation** — Two newly identified levees (Defenbaugh and Taylor-Chapman) require tracking documentation and confirmation of current FEMA protocol investigations for all identified levees before workmaps can proceed; (3) **Illinois River Floodplain Redelineation** — 46 miles of Illinois River floodplain must be redelineated using 2012 LiDAR topographic data to achieve consistent tie-in with the updated tributary Zone AE studies (previous delineation used 1998–2001 photogrammetry DTM).
- **Deliverables:** 2D HEC-RAS Kickapoo Creek model and revised 1D models; levee tracking documentation; Illinois River redelineation (46 miles, 2012 LiDAR); QR3/KDP-3 deliverable package

- **Period:** Per Cooperative Agreement Award Notice (FFY2020; June 2020 MAS date)
 - **Budget:** \$148,700 (FEMA)
 - **Multi-year:** Yes — 5th generation project since 2011. After QR3/KDP-3, a Preliminary/PPP MAS will be required for distribution, due process, and Final FIRM. The Lonza/Evonik levee issue was previously unresolved at ISWS13-05 and must be confirmed resolved by FEMA Region 5 before Preliminary can proceed.
 - **Recommended Next Steps:** Complete 2D Kickapoo Creek modeling; resolve Defenbaugh/Taylor-Chapman levee status with FEMA; complete Illinois River redelineation; advance to QR3/KDP-3; then scope a Preliminary + PPP MAS for Peoria County countywide DFIRM completion
-

ISWS_20_LOMR: LOMR Review Partners — Statewide Illinois

- **Activity Type:** LOMR/CLOMR Technical Review (statewide pilot program, not flood risk mapping)
 - **Phase:** Ongoing annual review program; this MAS continues ISWS's role as FEMA's delegated CLOMR/LOMR review authority for the entire State of Illinois
 - **Scope:** ISWS assumes responsibility for evaluating all CLOMR and LOMR requests submitted for the entire State of Illinois, reviewing engineering submittals against 44 CFR Part 65 requirements, and recommending approval or denial to FEMA for final determination. The program is treated as a pilot; FEMA makes all final determinations. Cases involving large-scope revisions that warrant PMRs are outside this MAS's scope (PMR funding addressed separately). Budget is based on ~37 applications at ~\$10,000/application. Exceeding available funding requires written notification to FEMA to arrange amendment or cost-share.
 - **Deliverables:** Technical review reports and approval recommendations for CLOMR/LOMR applications statewide; potential violation documentation coordinated with FEMA HQ; compliance with 44 CFR 60.3 review standards
 - **Period:** Award through **June 30, 2022** (explicitly stated — unique among this portfolio in specifying an end date)
 - **Budget:** \$371,740 (FEMA); ~\$10,000/application, ~37 estimated applications
 - **Multi-year:** Yes — LOMR Review Partners is a recurring annual program with future eligibility based on quality review performance. Explicitly anticipates future awards.
 - **Recommended Next Steps:** Process all incoming CLOMR/LOMR applications through FY2022 period of performance; monitor application volume vs. budget; if volume exceeds estimates, notify FEMA promptly for amendment; prepare for re-award evaluation at end of performance period
-

Cross-Cutting Observations

1. Pipeline Structure: Three Distinct Tiers

The FY20 portfolio divides cleanly into tiers:

- **Tier 1 – Completion** (Clay, Effingham, Cook/Kane): All three are late-stage, executing QR3 through Final Maps. These should produce effective FIRMs within the FY20–22 performance period.
- **Tier 2 – Mid-stream / Technical Blockers** (Rock River, Turtle Creek, Peoria): Studies have substantial prior investment but face specific unresolved technical or coordination issues before they can advance. Peoria is closest to completion (targeting QR3); Rock River and Turtle Creek need FRR before preliminary.

- **Tier 3 – Early Data Development** (Bureau, Johnson, Massac, Pope, Wayne-Skillet, Kishwaukee): All end at KDP-2. None will produce a DFIRM under this grant; all require at least one additional MAS cycle for DFIRM production. **This represents the majority of the portfolio budget (~\$4.24M of \$5.71M).**

2. Long-Running Projects Dominate

Many projects trace back many years:

- **Peoria:** 5 MAS generations since FFY2011 (ISWS11-16 → 12-05 → 13-05 → 18-04 → 20-13)
- **Rock River:** Started with a 2014 FEMA study, then ISWS17-06, now ISWS20-05
- **Turtle Creek:** ISWS15-04 → ISWS17-05 → ISWS20-06
- **Clay & Effingham:** Both trace to ISWS17-03

3. Southern Illinois Concentration

Three new Data Development projects (Johnson, Massac, Pope) are all in southern Illinois counties along the Ohio River. All three involve Ohio River redelineation, datum conversion (NGVD29→NAVD88), coordination with the Kentucky Division of Water, and major levee system considerations (Reevesville, Brookport, Golconda). These projects would benefit from coordinated scheduling and shared boundary condition data. None of these counties have had prior Discovery, and each will require a future DFIRM production MAS.

4. Kishwaukee as Largest Investment / Longest Horizon

At \$1.37M, Kishwaukee (ISWS_20-12) is the single largest project in the FY20 portfolio and is explicitly described as the first of at least four separate MAS grants. This is a 10–15 year commitment to bring the entire Kishwaukee HUC8 to updated DFIRM standards. Discovery (MAS17-02) has been completed; Phase 1 initiates H&H for Winnebago County. Planning for Phases 2–4 (Boone County, McHenry County, tributary HUC-10s) should begin concurrently with Phase 1 execution.

5. Bureau County — Potential Green River Watershed Coordination

The Bureau County study (ISWS_20-07) includes Green River reaches in four counties (Bureau, Henry, Whiteside, Lee) because of model tie-in requirements. ISWS notes this will "facilitate future mapping updates in the Green HUC8 watershed." A future HUC8-level MAS for the Green River watershed may be warranted, building on the Bureau County H&H investment.

6. Levees as a Recurring Risk Factor

Nearly every project in the portfolio identifies levees as a significant risk factor or scope driver: Tiskilwa Levee (Bureau), Karnak/Cache River Levee (Johnson), Brookport/Reevesville Levees (Massac), Golconda/Reevesville Levees (Pope), multiple levees in Wayne County (Skillet), Defenbaugh/Taylor-Chapman/Lonza/Evonik Levees (Peoria), East Moline levees (Rock River), and Turtle Creek railroad embankment (treated as de facto levee). In nearly all cases, levee LAMP outreach and hydraulic significance analysis are deferred to FEMA/RSC (STARR II), which creates schedule risk for downstream DFIRM production.

7. Future MAS Requirements — Budget Planning Signal

At minimum, the following future MAS grants will be needed to complete the FY20 projects:

- Bureau County: 1 DFIRM production MAS (QR3 → Final)
- Johnson County: 1 DFIRM production MAS
- Massac County: 1 DFIRM production MAS
- Pope County: 1 DFIRM production MAS
- Wayne County (combined Skillet + Little Wabash): 1 combined DFIRM production MAS
- Kishwaukee HUC8: 3+ additional data development MASs + 1 DFIRM production MAS
- Peoria County: 1 Preliminary/PPP completion MAS
- Rock River: 1–3 PMR production MASs (after FRR)
- Turtle Creek: 1 Preliminary/PPP MAS for both IL and WI panels