

FFY2024 MAS Portfolio Summary

Overview

The FFY2024 portfolio contains **10 base MAS/SOW agreements** plus **8 scope amendments** (designated "A" suffixes), for 18 total documents. The 10 base agreements represent: 1 Program Management (PM) SOW, 1 Community Outreach and Mitigation Strategies (COMS) SOW, and 8 Flood Risk Project (FRP) Mapping Activity Statements covering distinct geographic areas across Illinois. All agreements run under the Illinois State Water Survey (ISWS) Cooperating Technical Partners (CTP) program, FEMA Region 5, with Glenn Heistand as CTP Project Manager.

Total FEMA Funding (base MAS/SOWs): ~\$3,241,000

The 8 "A" amendments (24-02A through 24-10A) are administrative scope modifications with no new funding — all identically remove references to the Climate and Economic Justice Screening Tool (CEJST) and equity-related indices (Social Vulnerability Index, National Risk Index, Community Disaster Resiliency Zones) from community assessment and stakeholder engagement tasks. These were signed by Glenn Heistand on 05/28/2025, with FEMA countersignatures pending as of that date.

The FRP portfolio spans a wide range of project maturity: two projects are in active **data development** (pre-Preliminary), two are in **Preliminary map production** through Open House, one is in **QR1–QR3 Preliminary production** (not yet distributing), and three are in **Post-Preliminary Processing** (the final phase before effective maps). Period of performance for all projects: **10/1/2024 – 9/30/2027**.

Projects

ISWS_24-01: Program Management (PM) — Statewide Illinois

- **Activity Type:** Program Management (PM) — cannot produce a FIRM
- **Phase:** Ongoing programmatic management (not tied to a single mapping phase)
- **Scope:** Supports all FFY2024 FRP mapping activities statewide through four selected tasks: (1) joint ISWS/IDNR-OWR Business Plan documenting Illinois flood mapping needs; (2) Global Program Management including risk assessments, Earned Value reporting, and CTP Performance Metrics; (3) CNMS spatial database maintenance at four project life-cycle points (Funded → DFIRM Production → Preliminary → LFD); and (4) Programmatic QA/QC Plan with CFM credential maintenance and updated checklists.
- **Deliverables:** Business Plan; Global Program Management Plan; CNMS database updates; Programmatic QA/QC Plan with updates
- **Period:** 10/01/2024 – 09/30/2026
- **Budget:** \$95,000 (FEMA only; no partner leverage)
- **Multi-year:** Yes — two-year performance period; Business Plans are annually updated; CNMS tracking continues throughout all active FRP project lifecycles

- **Recommended Next Steps:** (1) Complete Business Plan to document statewide mapping priorities for future Risk MAP cycles; (2) Maintain CNMS updates at each life-cycle KDP for all active FRP projects (24-03 through 24-10); (3) Finalize Programmatic QA/QC Plan and ensure CFM credentials remain current; (4) Confirm COMS SOW (24-02) remains funded — if not, add Global Outreach (Task 3) and Mentoring (Task 8) to this PM SOW per the contingency clause.

ISWS_24-02: Community Outreach and Mitigation Strategies (COMS) — Statewide Illinois

- **Activity Type:** Community Outreach and Mitigation Strategies (COMS) — cannot produce a FIRM
- **Phase:** Outreach/engagement and mitigation support (runs parallel to FRP mapping activities)
- **Scope:** Six selected outreach tasks: (1) COMS Engagement Plan (combined with Business Plan); (2) Strategic Planning for community outreach partnerships, including StoryMaps of flood event impacts, South Beloit/Turtle Creek (USACE coordination), and Kishwaukee watershed stakeholder engagement; (4) Mitigation Support identifying communities for future reconnaissance studies; (5) Communication & Outreach including illinoisfloodmaps.org website, tutorial videos, and statewide contact database; (6) Training materials (NFIP 101, MT-2, LOMR, technical workshops); (7) Mitigation Planning Technical Assistance with online resilience toolkit; (9) Mentoring with CTP entities and sharing tools/best practices on FEMA CTP Collaboration Center.
- **Deliverables:** COMS Engagement Plan; StoryMaps; South Beloit coordination summary; training materials; illinoisfloodmaps.org updates; mitigation resource toolkit; mentoring report; prioritized community list for future mapping reconnaissance
- **Period:** 10/01/2024 – 09/30/2026
- **Budget:** \$200,000 (FEMA only)
- **Multi-year:** Yes — two-year performance period; builds on CTP partnership since 2008/2013; Task 4 community list feeds future Risk MAP project scoping
- **Recommended Next Steps:** (1) Complete COMS Engagement Plan concurrent with PM Business Plan; (2) Use South Beloit/Turtle Creek USACE coordination and Kishwaukee engagement outputs to feed future MAS scoping; (3) Convert Task 4 community prioritization list into formal reconnaissance/scoping for future FRP MAS awards; (4) Maintain illinoisfloodmaps.org as a resource hub for active FRP due-process notices (appeal periods, open houses) for 24-03 through 24-07 projects.

Note on 24-02A Amendment: Removes equity/CEJST/CDRZ language from Section 2.2 Strategic Planning scope. No budget change. FEMA countersignature pending as of 05/28/2025.

ISWS_24-03: Peoria County, IL — DFIRM Post-Preliminary Processing

- **Activity Type:** Countywide digital-FIRM (DFIRM) — Due Process, Final Map Production & Distribution, Revalidation
- **Phase:** Post-Preliminary Processing — **the final phase before effective maps.** Preceded by ISWS 23-03 (through Public Open House).

- **Scope:** This MAS picks up after the Public Open House completed under ISWS 23-03. Work covers: managing the 90-day statutory appeal period (KDP4), resolving all appeals and comments, producing final FIRM panels (118 total panels, 18 communities) via FEMA AMP tool, processing the Letter of Final Determination (KDP5), distributing revalidation letters, and archiving. Incorporates engineering studies from MAS ISWS 11-16 (Zone A), ISWS 18-04 and ISWS 20-03 (Zone AE), and ISWS 21-09 (Spoon River re-delineation). Multiple levees in the study area are tracked through the National Levee Database, with mapping paths ranging from Natural Valley to Accredited status. Watersheds: Spoon, Lower Illinois–Senachwine Lake, Lower Illinois–Lake Chautauqua, Mackinaw.
- **Deliverables:** Due Process documentation (affidavits, appeal/comment records); Final FIRM Database (QR5–QR7); Final FIS Report; revalidation letters; TSDN archive; LFD
- **Period:** 10/01/2024 – 09/30/2027
- **Budget:** \$135,240 (FEMA only)
- **Multi-year:** Yes — continuation of a long multi-phase effort: ISWS 11-16 → ISWS 18-04/20-03 → ISWS 21-09 → ISWS 23-03 (Open House) → ISWS 24-03 (Post-Prelim / Final). This is the terminal MAS for Peoria County effective maps.
- **Recommended Next Steps:** (1) Initiate 90-day appeal period — submit KDP4, publish Federal Register FHD notice, send CEO/FPA notification letters, publish news releases; (2) Resolve all appeals and comments with FEMA-letterhead correspondence and revised analyses as needed; (3) Pass National QR5 and QR7; (4) Submit KDP5 for LFD; (5) Pass QR6 for Final SOMA and Final FHD notice; (6) Submit AMP-produced final FIRM/FIS for printing (pass QR7/QR8); (7) Process revalidation letters 4–5 weeks before effective date; (8) Archive to TSDN/FEDD. Key risk: levee NLD delays — maintain close coordination with FEMA Region 5 RSC Levee Lead.

Note on 24-03A Amendment: Removes CEJST/equity language from Watershed Assessment and Stakeholder Engagement tasks. No budget change. FEMA countersignature pending.

ISWS_24-04: McHenry County, IL — Nippersink PMR Post-Preliminary Processing

- **Activity Type:** Limited-panel Physical Map Revision (PMR) — Post-Preliminary Processing (Due Process, Final Map Production & Distribution, Revalidation)
- **Phase:** Post-Preliminary Processing — **the final phase before effective maps.** Preceded by ISWS 23-04 (through Public Open House).
- **Scope:** This MAS covers the final 15-panel update to the McHenry County FIRM within the Nippersink Creek and North Branch Nippersink Creek HUC-10 watersheds. Work includes: managing the 90-day statutory appeal period, resolving appeals/comments, producing final FIRM panels for 8 communities via AMP tool, processing the LFD (KDP5), distributing revalidation letters, and archiving. Incorporates engineering from MAS IDNR-ISWS 15-01 and ISWS 19-09. Leverages Zone A tributary studies completed by FEMA Region V contractors in 2016.
- **Deliverables:** Due Process documentation; Final 15-panel FIRM update; Final FIS Report (upgraded to current standards); revalidation letters; TSDN archive; LFD

- **Period:** 10/01/2024 – 09/30/2027
- **Budget:** \$121,810 (FEMA only)
- **Multi-year:** Yes — continuation: IDNR-ISWS 15-01 → ISWS 19-09 → ISWS 23-04 (Open House) → ISWS 24-04 (Post-Prelim / Final). Terminal MAS for this 15-panel PMR.
- **Recommended Next Steps:** Same post-preliminary workflow as 24-03: (1) KDP4 / 90-day appeal period initiation; (2) appeals resolution; (3) QR5/QR7 final map review; (4) KDP5 / LFD; (5) QR6 / Final SOMA and FHD notice; (6) Final FIRM printing (QR7/QR8); (7) Revalidation letters; (8) Archive. Key risk: manage community FPM relationships to minimize appeals; coordinate with FEMA Region 5 on any NLD updates.

Note on 24-04A Amendment: Removes CEJST/equity language. No budget change. FEMA countersignature pending.

ISWS_24-05: McDonough County, IL — DFIRM Post-Preliminary Processing

- **Activity Type:** Countywide digital-FIRM (DFIRM) — Post-Preliminary Processing (Due Process, Final Map Production & Distribution, Revalidation)
- **Phase:** Post-Preliminary Processing — **the final phase before effective maps**. Preceded by ISWS 23-05 (through Public Open House).
- **Scope:** Obtains effective countywide DFIRM for McDonough County (42 total FIRM panels, 12 communities, watersheds: Flint-Henderson, La Moine, Spoon, Lower Illinois-Lake Chautauqua). Incorporates Zone A and Zone AE engineering from ISWS 19-04. Work covers: 90-day statutory appeal period, appeals/comments resolution, final FIRM production via AMP tool, LFD processing, revalidation letters, and archiving.
- **Deliverables:** Due Process documentation; Final 42-panel DFIRM; Final FIS Report; revalidation letters; TSDN archive; LFD
- **Period:** 10/01/2024 – 09/30/2027
- **Budget:** \$118,150 (FEMA only)
- **Multi-year:** Yes — continuation: ISWS 19-04 (data dev) → ISWS 23-05 (Open House) → ISWS 24-05 (Post-Prelim / Final). Terminal MAS for McDonough County effective maps.
- **Recommended Next Steps:** Same as 24-03/24-04: (1) KDP4 / 90-day appeal period; (2) resolve appeals; (3) QR5/QR7; (4) KDP5/LFD; (5) QR6 Final SOMA/FHD; (6) Final FIRM printing; (7) Revalidation letters; (8) Archive. Also: (9) Monitor NLD for any levee-related schedule impacts (levee records appear to be illustrative template entries — verify actual McDonough County levee inventory).

Note on 24-05A Amendment: Removes CEJST/equity language. No budget change. FEMA countersignature pending.

ISWS_24-06: Johnson County, IL — DFIRM QR1 through Open House (Preliminary Phase)

- **Activity Type:** Countywide digital-FIRM (DFIRM) — Preliminary Map Production (Draft FIRM Database → Preliminary Map Products → CCO Meeting → Public Open House)
- **Phase:** Preliminary production phase (QR1 through distribution and Open House). **Due Process and Final Map Production deferred to a subsequent MAS.**
- **Scope:** Produces a Preliminary Johnson County DFIRM (32 panels, 8 communities, watersheds: Big Muddy, Saline, Lower Ohio-Bay, Lower Ohio, Cache). Incorporates Zone A/AE engineering from ISWS 20-08 and the ISWS 2D regional analysis of the Cache River Valley. Work includes: Draft FIRM Database production (QR1), Preliminary FIRM panels and FIS via AMP tool (QR3), CCO meeting, and Public Open House. Explicitly excluded from this MAS: Due Process, Final Map Production, and Flood Risk Products development. Two non-accredited levees in the study area (Cache River Levee/Karnak Levee and Reevesville Levee) mapped as Natural Valley — potential schedule risk from ongoing maintenance and possible accreditation pursuit.
- **Deliverables:** Draft FIRM Database (QR1); Preliminary FIRM panels + FIS Report (QR3); CCO Meeting documentation; Open House documentation; Project Communication Plan
- **Period:** 10/01/2024 – 09/30/2027
- **Budget:** \$212,010 (FEMA only)
- **Multi-year:** Yes — continuation: ISWS 20-08 (data dev) → ISWS 24-06 (Preliminary). **A future MAS is explicitly required** to cover Due Process (90-day appeal), Final Map Production, LFD, and Flood Risk Products.
- **Recommended Next Steps:** (1) Finalize Draft FIRM Database; pass QR1/DVT; (2) Produce Preliminary FIRM panels via AMP tool; pass QR2 and QR3; (3) Distribute Preliminary products; (4) Hold CCO meeting and Public Open House; (5) **Initiate a new MAS for Post-Preliminary Processing** — 90-day appeal period, appeals resolution, Final FIRM (QR5-QR8), LFD, revalidation; (6) Continue levee coordination — USACE, IDNR/OWR, and FEMA R5 engagement on Cache River and Reevesville levees.

Note on 24-06A Amendment: Removes CEJST/equity language. No budget change. FEMA countersignature pending.

ISWS_24-07: Bureau County, IL — Countywide PMR QR1 through Open House (Preliminary Phase)

- **Activity Type:** Countywide Physical Map Revision (CW-PMR) — Preliminary Map Production (Draft FIRM Database → Preliminary Map Products → CCO Meeting → Public Open House)
- **Phase:** Preliminary production phase (QR1 through distribution and Open House). **Due Process and Final Map Production deferred to a subsequent MAS.**
- **Scope:** Produces a Preliminary Bureau County FIRM update (73 panels, 26 communities, watersheds: Lower Rock, Lower Illinois–Senachwine Lake, Green, Spoon). Incorporates Zone A/AE engineering from ISWS 20-07, Illinois River re-delineation, and Big Bureau Creek analysis. Updates FIS format to current FEMA standards. Includes upgrade of Tiskilwa Levee status from PAL (expired) to "Not Accredited" — two Tiskilwa

levee systems create schedule risk. Explicitly excluded: Due Process, Final Map Production, Flood Risk Products.

- **Deliverables:** Draft FIRM Database (QR1); Preliminary FIRM panels + FIS Report (QR3); CCO Meeting documentation; Open House documentation; Communication Plan
- **Period:** 10/01/2024 – 09/30/2027
- **Budget:** \$239,010 (FEMA only)
- **Multi-year:** Yes — continuation: ISWS 20-07 (data dev) → ISWS 24-07 (Preliminary). **A future MAS is explicitly required** for Post-Preliminary Processing (Due Process, Final Map Production, LFD, Flood Risk Products).
- **Recommended Next Steps:** (1) Complete Draft FIRM Database; pass QR1/DVT; (2) Produce Preliminary FIRM panels via AMP tool; pass QR2/QR3; (3) Distribute Preliminary products; (4) Hold CCO meeting and Public Open House; (5) **Initiate a new MAS for Post-Preliminary Processing**; (6) Resolve QR3 comments promptly to avoid delays to the next MAS start; (7) Continue engagement with Tiskilwa Levee owners (STARR II LAMP 2017 precedent) and USACE/RSC to define accreditation/non-accreditation path before Due Process.

Note on 24-07A Amendment: Removes CEJST/equity language. No budget change. FEMA countersignature pending.

ISWS_24-08: Kishwaukee Watershed — Data Development Phase 5

- **Activity Type:** Survey, Hydrology, and Hydraulic Data Development (multi-phase tributary update program)
- **Phase:** Data Development Phase 5 — pre-Preliminary. **Preliminary and Post-Preliminary map production will require future MASs.**
- **Scope:** New survey, hydrology, hydraulic analysis, and floodplain re-delineation for 186 miles of Kishwaukee River tributaries across three HUC-10 watersheds (Coon Creek, East Branch Kishwaukee, South Branch Kishwaukee) within DeKalb, Kane, and McHenry counties. Methodology: ~173 miles Zone A (1D steady-state and 2D Rain on Mesh using HEC-RAS), ~13 miles Zone AE with new floodway analysis (1D). This is Phase 5 of a continuing effort to update all CNMS unverified streams in the Kishwaukee HUC-8 subbasin (07090006). Results will eventually support Physical Map Revisions (PMRs) for DeKalb, Kane, and McHenry counties. Risks: levees identified through modeling, survey acquisition delays, new LiDAR availability mid-project.
- **Deliverables:** Survey data (spatial files, photos, sketches, as-built data) — due November 2026; Hydrology data; Hydraulics simulations and FIS profile inserts; Floodplain mapping spatial files; QA/QC documentation for all tasks
- **Period:** 10/01/2024 – 09/30/2027
- **Budget:** \$963,000 (FEMA only) — largest FRP engineering project in the FFY2024 portfolio
- **Multi-year:** Yes — explicitly Phase 5 of a multi-phase program. Prior phases updated other portions of the Kishwaukee HUC-8. **Multiple future MASs explicitly anticipated** for Draft FIRM Database, Preliminary Map Products, and Post-Preliminary Processing for DeKalb, Kane, and McHenry county PMRs.
- **Recommended Next Steps:** (1) Contract for survey work early (largest schedule risk); (2) Begin stakeholder coordination with DeKalb, Kane, McHenry county FPMs and municipalities; (3) Complete hydrology (USGS

StreamStats / 2D Rain on Mesh) and hydraulic models (HEC-RAS) by 9/30/2027; (4) Monitor ISGS Height Modernization Team monthly for new LiDAR availability; (5) Upon deliverable completion, **initiate a Draft FIRM/Preliminary MAS** for 3-county PMR production; (6) If any levees are identified through modeling, immediately coordinate with FEMA Region 5 RSC Levee Lead.

Note on 24-08A Amendment: Removes CEJST/equity language. No budget change. FEMA countersignature pending.

ISWS_24-09: Macoupin County, IL — DFIRM QR1 through QR3 (Preliminary Production)

- **Activity Type:** Countywide digital-FIRM (DFIRM) — Preliminary Map Production (Draft FIRM Database through Preliminary Map Products only — distribution deferred)
- **Phase:** Preliminary production phase (QR1–QR3). **Preliminary distribution, CCO meeting, Open House, and all Post-Preliminary tasks deferred to subsequent MASs.**
- **Scope:** Produces a Preliminary Macoupin County DFIRM (73 panels, 28 communities, 7 watersheds: South Fork Sangamon, Lower Illinois, Macoupin, Shoal, Peruque-Piasa, Cahokia-Joachim, Lower Kaskaskia). Incorporates Zone A/AE engineering from ISWS 19-05. This MAS stops at QR3 — the Distribute Preliminary Products task (Task 23) is explicitly excluded and will require a separate future MAS. Risk: substantial QR3 comments could delay the start of the distribution MAS.
- **Deliverables:** Draft FIRM Database metadata and files (QR1); Preliminary FIRM panels via AMP tool; Preliminary FIS Report; Preliminary/Revised Issuance Letters; Preliminary SOMAs; Pre- and Post-QR3 documentation
- **Period:** 10/01/2024 – 09/30/2027
- **Budget:** \$170,150 (FEMA only)
- **Multi-year:** Yes — continuation: ISWS 19-05 (data dev) → ISWS 24-09 (QR1–QR3). **Two future MASs anticipated:** one for Preliminary Distribution/CCO/Open House (Task 23 + early Task 24), and one for full Post-Preliminary Processing (Due Process, Final Map Production, LFD).
- **Recommended Next Steps:** (1) Complete Draft FIRM Database; pass QR1/DVT; (2) Produce Preliminary FIRM panels via AMP tool; aim for 0–1 QR3 recycles to minimize delays; (3) Pass QR3; (4) **Initiate a new MAS for Preliminary Distribution** (Task 23 — KDP3, transmittal to communities, State NFIP Coordinator, public); (5) **Plan a further MAS for Post-Preliminary Processing** — CCO meeting, Open House, 90-day appeal, Final FIRM, LFD; (6) Begin community communications with Macoupin County FPMs early to minimize future appeals.

Note on 24-09A Amendment: Removes CEJST/equity language. No budget change. FEMA countersignature pending.

ISWS_24-10: Embarras River Tributaries — Data Development

- **Activity Type:** Survey, Hydrology, and Hydraulic Data Development (large-scale multi-county tributary study)
- **Phase:** Data Development — pre-Preliminary. **Preliminary and Post-Preliminary production will require future MASs.**
- **Scope:** New survey, hydrology, hydraulic analysis, and floodplain re-delineation for **1,049 miles** of Embarras River tributaries across 9 HUC-10 watersheds (Big Creek, Brushy Creek, East Crooked Creek, Honey Creek, Indian Creek, Muddy Creek, North Fork Embarras, Paul Creek, Range Creek) within 7 counties (Clark, Coles, Crawford, Cumberland, Edgar, Jasper, Lawrence). Methodology: ~1,035 miles Zone A (2D "Rain on Mesh" HEC-RAS using Bulletin 75 storms); ~14 miles Zone AE (1D steady-state HEC-RAS); plus Zone AE re-delineation on current topography for 3 streams in Lawrence County (Brushy Creek, Muddy Creek, Shirley Creek — 11.2 miles total). Eight non-accredited levees in the study area with mapping path TBD. Future regulatory outcomes include a first-time countywide DFIRM for Jasper County and DFIRM updates for Lawrence, Crawford, and Clark counties; Coles, Cumberland, and Edgar county mapping not yet determined.
- **Deliverables:** Survey data (due June 2026); Hydrology data; Hydraulics models and FIS inserts; Floodplain mapping spatial files including Zone AE re-delineation; QA/QC documentation
- **Period:** 10/01/2024 – 09/30/2027
- **Budget:** \$986,630 (FEMA only) — second-largest project in FFY2024 portfolio
- **Multi-year:** Yes — builds on prior Embarras mainstem MASs. **Multiple future MASs explicitly required** to reach effective FIRMs for Jasper, Lawrence, Crawford, Clark, and potentially other Embarras counties.
- **Recommended Next Steps:** (1) Contract for survey work early (largest schedule risk — vast geographic scope at 1,049 miles); (2) Coordinate with Lawrence County on existing 2020 LiDAR for Zone AE re-delineation streams; (3) For the 8 non-accredited levees, form Local Levee Partnership Teams (LLPTs) early and confirm mapping path forward (Natural Valley, Certify, or Accredited) with FEMA R5 RSC Levee Lead before hydraulic modeling; (4) Upon completion, **initiate Draft FIRM/Preliminary MASs** for Jasper (first-time DFIRM), Lawrence, Crawford, and Clark counties; (5) Coordinate with FEMA R5 on scope for Coles, Cumberland, and Edgar county mapping needs; (6) Monitor ISGS Height Modernization Team for new LiDAR availability.

Note on 24-10A Amendment: Removes CEJST/equity language. No budget change. FEMA countersignature pending.

Cross-Cutting Observations

1. Portfolio Maturity Ladder

The FFY2024 FRP portfolio spans all stages of the FIRM production lifecycle simultaneously:

Stage	Projects
Data Development (pre-Preliminary)	24-08 (Kishwaukee Phase 5), 24-10 (Embarras Tributaries)

Stage	Projects
Preliminary Production (QR1–QR3 only)	24-09 (Macoupin)
Preliminary Production + Open House	24-06 (Johnson), 24-07 (Bureau)
Post-Preliminary / Final (terminal MAS)	24-03 (Peoria), 24-04 (McHenry Nippersink), 24-05 (McDonough)
PM/COMS (support)	24-01 (PM), 24-02 (COMS)

Three projects (24-03, 24-04, 24-05) are the closest to final effective FIRM maps — all are in Post-Preliminary Processing (Due Process through LFD). These should be prioritized for close coordination during the appeal period.

2. Large Data Development Investment

Nearly **\$1.95 million (60%)** of the \$3.24M FRP budget is in data development (24-08 Kishwaukee at \$963K and 24-10 Embarras at \$986K). These projects will not produce FIRMs by themselves — each will require 2–3 additional MASs (Preliminary, Post-Preliminary) before reaching effective maps. The Embarras study alone covers 7 counties and 1,049 miles of streams, making it the most geographically extensive project in the portfolio.

3. Pipeline Gap — Future MAS Needs Are Explicit

Five of the eight FRP projects explicitly defer major workflow phases to future (currently unfunded) MASs:

- **24-06 (Johnson):** Needs Post-Preliminary MAS for Due Process, Final Map Production, LFD
- **24-07 (Bureau):** Needs Post-Preliminary MAS for Due Process, Final Map Production, LFD
- **24-09 (Macoupin):** Needs a Preliminary Distribution MAS (Task 23) *and* a Post-Preliminary MAS
- **24-08 (Kishwaukee):** Needs Draft FIRM/Preliminary MAS *and* Post-Preliminary MAS for 3 counties (DeKalb, Kane, McHenry)
- **24-10 (Embarras):** Needs multiple Preliminary and Post-Preliminary MASs for up to 7 counties

This represents a significant forward-funding requirement that should be captured in future FFY Business Plans.

4. Recurring Watersheds and Multi-Phase History

- **Kishwaukee River basin** appears in both 24-02 (COMS stakeholder engagement) and 24-08 (Phase 5 data development), reflecting a long-running multi-phase study effort.
- **Spoon watershed** appears in both Peoria County (24-03) and McDonough County (24-05), reflecting the shared hydrology of central Illinois.
- Several projects reference engineering from MASs stretching back to 2011 (ISWS 11-16 for Peoria) and 2015 (ISWS 15-01 for McHenry), illustrating that effective FIRMs in complex counties may require 10–15 years of cumulative MAS work.

5. Blanket CEJST Amendment — All A-Suffix Documents

All 8 "A" amendments (24-02A through 24-10A) are **identical in structure and purpose**: removing Climate and Economic Justice Screening Tool (CEJST) and related equity-index language (SVI, NRI, CDRZ) from Sections 2.3.3 and 2.4.1 of each MAS. These were signed by Glenn Heistand on 05/28/2025. As of that date, **all 8 still**

awaited FEMA Region 5 countersignature (John Wethington's date field was blank in every document). These amendments should be tracked for full execution.

6. Levee Risk Is Pervasive

Levee coordination is a named schedule risk in six of eight FRP projects:

- **24-03 (Peoria):** 10+ levee systems in NLD with varied accreditation status
- **24-04 (McHenry):** No specific levees named but risk flag present
- **24-05 (McDonough):** Levee inventory needs verification (table appears templated)
- **24-06 (Johnson):** Two non-accredited levees (Cache River/Karnak, Reevesville) mapped as Natural Valley
- **24-07 (Bureau):** Two Tiskilwa levees with expired PAL status
- **24-10 (Embarras):** Eight non-accredited levees with mapping path TBD

Early and continuous engagement with the FEMA Region 5 RSC Levee Lead is critical across the portfolio.

7. Budget Summary

Project	FEMA Funding
ISWS 24-01 (PM)	\$95,000
ISWS 24-02 (COMS)	\$200,000
ISWS 24-03 (Peoria Post-Prelim)	\$135,240
ISWS 24-04 (McHenry PMR Post-Prelim)	\$121,810
ISWS 24-05 (McDonough Post-Prelim)	\$118,150
ISWS 24-06 (Johnson Preliminary)	\$212,010
ISWS 24-07 (Bureau PMR Preliminary)	\$239,010
ISWS 24-08 (Kishwaukee Data Dev Ph.5)	\$963,000
ISWS 24-09 (Macoupin QR1–QR3)	\$170,150
ISWS 24-10 (Embarras Data Dev)	\$986,630
TOTAL	\$3,241,000

All "A" amendments (\$0 additional funding) are excluded from this total.